

Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 2177851020

FOR OFFICE USE ONLY

Facility # 5018242 Permit # 00950-2022REM Request Rec'd 09/01/2022 Amended Date Approval Date 9/1/2022 DS Permit Expires 3/1/2023

Permit for REMOVAL of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to remove underground storage tank(s) or piping is hereby granted. Such removal shall not commence until the contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall establish a date certain to perform the UST activity by contacting the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety, at which time the UST activity shall be scheduled. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business

entity:

Beardstown Cusd #75 515 Canal Street Beardstown, IL 62618

Contact: (217) 323-3079

(2) <u>FACILITY</u> - name and address where tanks are located:

Beardstown High School 200 E 15Th St Beardstown, IL 62618

Contact: Schaeffer Allen (217) 323-5179

(3) REMOVAL OF TANKS:

- (a) Number and size of tanks being removed: (TK # 1) 12,000
- (b) Description/location of piping being removed:
- (c) Product to be stored in each tank: (TK # 1) Heating Oil
- (d) Reason of tanks being removed:
- (e) If tank(s) is leaking, indicate IEMA incident number:
- (f) Date each tank was last used: (TK # 1) 3/1/1969
- (4) The owner must notify this Office when completion of tank removal has occurred, on the Notification for Underground Storage Tank Form. This form can be obtained at www.sfm.illinois.gov or by calling (217)785-1020. After removal is completed, the owner/operator shall perform a site assessment by measuring for the presence of a release where contamination is most likely to be present at the UST site. This is in accordance with the Illinois Administrative Code 176.360 (a) regulations and 40 CFR Part 280.72 (a) Federal Register Requirement.
- (5) <u>SPECIAL CONTINGENCIES</u>: UST is located near existing school buildings. A sheet pile coffer dam will be constructed around the UST before any significant excavation commences. The UST will be uncovered to the extent the sand currently inside the UST can be removed using a vacuum truck. Sand will be staged on a temporary containment for load out and transportation to Hickory Creek Landfill in Bayliss IL. UST will be removed from the ground, cut open, pressure washed clean, and transported to a steel recycling facility. After collecting soil confimation samples the excavation will be filled with lean concrete (flowable fill). Sheet pile coffer dam will be removed.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

EnviroServe, Inc. Contact Person: Bob Rogers 5350 East Firehouse Road Phone: (217) 428-4381

Decatur, IL 62521 Contractor Registration # IL002450 Exp. 2/22/2023

Sincerely,

Daniel Starks

Oaniel J. Starke

cc: Storage Tank Safety Specialist Division File