



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

Extended

FOR OFFICE USE ONLY

Facility # 2047334
Permit # 01255-2021INS
Request Rec'd 11/01/2021
Amended Date
Approval Date 11/1/2021 DS
Permit Expires 5/3/2023

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Rohlwing & Devon LLC 5277 Trillium Boulevard Hoffman Estates, IL 60192 Contact: Rick Heidner (630) 894-0099	(2) FACILITY - name and address where tanks are located: Ricky Rockets - Itasca 1221 N Rohlwing Rd Itasca, IL 60143 Contact: Eric Grabowski (630) 894-0099
-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

(3) INSTALLATION OF TANKS:

- (a) *Number and size of tanks being installed: (TK # 1, 5) - 20,000, (TK # 2, 4) - 6,000, (TK # 3) - 10,000*
- (b) *Type of tank(s): (TK # 1, 2, 3, 4, 5) Tank - Fiberglass Double Wall Containment Solutions*
- (c) *Type of piping: (TK # 1, 2, 3, 4, 5) Piping - Fiberglass Double Wall A.O. Smith from tanks to dispensers as shown in site plan, (TK # 1, 2, 3, 4, 5) Piping - Ball Valves, (TK # 1, 2, 3, 4, 5) Piping - Shear Valves, (TK # 1, 2, 3, 4, 5) Piping - Flex Connector Steel, (TK # 1, 2, 3, 4, 5) Piping - Single Wall STP/Tanktop Sump*
- (d) *Product to be stored in each tank: (TK # 1) - Gasoline - Regular, (TK # 2) - Gasoline - Premium, (TK # 3, 5) - Diesel Fuel, (TK # 4) - E-85*
- (e) *Type of leak detection being used:*
 - Tank: (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD, (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Non-Discriminating Interstitial Monitoring Sensors*
 - Piping: (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Electronic Pressurized Line Leak Detection, (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Non-Discriminating Sump Sensor with positive shutdown in all submersible and dispenser sumps*
- (f) *Corrosion Protection being used:*
 - Tank: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Piping - Fiberglass Non-Corrosive*
- (g) *Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3, 4, 5) Spill Contain Device - Double Wall Spill Bucket*
- (h) *Overfill prevention devices: (TK # 1, 2, 3, 4, 5) Overfill Prev Device - Overfill Drop Tube Valve, (TK # 1, 2, 3, 4, 5) Overfill Prev Device - Overfill Alarm*

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.

- (5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

(6) **SPECIAL CONTINGENCIES** : New build site. Installing (1) 20K Gal (regular), (1) 22K multi-compartment (prem/diesel/E85), (1) 20K (diesel), (1) 8K (DEF). Installing (14) new dispensers, sumps, islands. New canopy. New TLS450Plus

(6) **PERSON, FIRM OR COMPANY PERFORMING WORK:**

Stenstrom Petroleum Services Group
2422 Center Street
Rockford, IL 61108

Contact Person: Robert Stenstrom
Phone: (815) 398-6250
Contractor Registration # IL1890 Exp. 4/12/2022

Sincerely,

A handwritten signature in cursive script, reading "Daniel G. Starks", is written over a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist
Division File