



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

FOR OFFICE USE ONLY
Facility # 1-009851
Permit # 01146-2007INS
Request Rec'd 07/30/2007
Amended Date
Approval Date 7/31/2007 JC
Permit Expires 1/31/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Johnson Oil Company 1305 12th Avenue Rock Falls, IL 61071 Contact: Arthur J Johnson (815) 625-6380	(2) FACILITY - name and address where tanks are located: Express Lane #59 1441 N. Columbus Street Ottawa, LaSalle Co., IL Contact: Joe Bryant
--	--

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 6) - 20,000 gallons, (TK # 7, 8, 9) - 6,000 gallons
- (b) Type of tanks:** (TK # 6, 7, 8, 9) - (Installing) XERXES double wall fiberglass
- (c) Type of piping:** (TK # 6, 7, 8, 9) - (Installing) A.P.T. Poly Tech P175 SC double wall flexible
- (d) Product to be stored in each tank:** (TK # 6, 7, 9) - Gasoline, (TK # 8) - Diesel Fuel
- (e) Type of leak detection being used:**
 - Tank:** (TK # 6, 8) - (Installing) Veeder Root TLS300i automatic tank gauge probes only (console from old system will be re-used), (TK # 6, 7, 8, 9) - (Installing) Veeder Root TLS300i interstitial tank sensor, (TK # 7, 9) - Existing automatic tank gauging probes to be installed / re-used from the old system (existing console will be re-used).
 - Piping:** (TK # 6, 7, 9) - (Installing) FE Petro STP-MLD-E mechanical line leak detector, (TK # 6, 7, 8, 9) - (Installing) Veeder Root TLS300i interstitial piping sump sensor at each submersible sump and at the two northernmost dispenser sumps only. (TK # 8) - (Installing) European Suction
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 6, 7, 8, 9) - (Installing) Fiberglass
 - Piping:** (TK # 6, 7, 8, 9) - (Installing) Non-corrosive flexible
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.**

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u> Contact Person: Rob Vyncke Phone: Contractor Registration # Exp.

Sincerely,



cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)