**OFFICE OF THE ILLINOIS STATE FIRE MARSHAL**
**Division of Technical Services**
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

FOR OFFICE USE ONLY
Facility # 2-043724
Permit # 00984-2007INS
Request Rec'd 07/05/2007
Amended Date
Approval Date 7/6/2007 JC
Permit Expires 1/6/2008

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

| **(1) OWNER OF TANKS** - Corporation, partnership, or other business entity: | **(2) FACILITY** - name and address where tanks are located: |
|---|---|
| Enterprise<br>605 25th Street<br>Bellwood, IL 60104<br><br>Contact: | Enterprise Rent-A-Car<br>4025 N. Mannheim Rd.<br>Schiller Park, Cook Co., IL<br><br>Contact: |

**(3) INSTALLATION OF TANKS:**

***(a) Number and size of tanks being installed:*** (TK # 1) - 10,000 gallons, (TK # 2) - 6,000 gallons

***(b) Type of tanks:*** (TK # 1, 2) - (Installing) Glasteel II double wall composite

***(c) Type of piping:*** (TK # 1, 2) - (Installing) A.P.T. Poly Tech P200SC double wall flexible

***(d) Product to be stored in each tank:*** (TK # 1) - Gasoline, (TK # 2) - Diesel Fuel

***(e) Type of leak detection being used:***

***Tank:*** (TK # 1, 2) - (Installing) Veeder Root TLS 300 Interstitial tank sensor, (TK # 1, 2) - (Installing) Veeder Root TLS 300 automatic tank gauge

***Piping:*** (TK # 1, 2) - (Installing) European Suction, (TK # 1, 2) - (Installing) Veeder Root TLS 300 interstitial piping sump sensor at tanks only.

***(f) Corrosion Protection being used:***

***Tank:*** (TK # 1, 2) - (Installing) Composite

***Piping:*** (TK # 1, 2) - (Installing) Non-corrosive flexible

***(g) Spill containment devices:***

***(h) Overfill prevention devices:***

**(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.**

**(5) GENERAL REQUIREMENTS:**

**(6) SPECIAL CONTINGENCIES**:

**(7) PERSON, FIRM OR COMPANY PERFORMING WORK**:

Contact Person: Robert Sumoski
Phone:

Contractor Registration # Exp.

Sincerely,

James J. Coffey

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)