OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

Amended

FOR OFFICE USE ONLY
Facility # 2-010919
Permit # 00760-2007UPG
Request Rec'd 05/29/2007
Amended Date 07/02/2007
Approval Date 5/31/2007 JC
Permit Expires 11/30/2007

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for underground piping upgrade, leak detection, spill and overfill prevention of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

(1) OWNER OF TANKS - Corporation, partnership, or other business entity:	**(2) FACILITY** - name and address where tanks are located:
Wagemann Oil Co. 381 E. St. Charles Rd. Carol Stream, IL 60188 Contact: Peter Spina (630) 668-0141	Villa Park Citgo 151 W North Ave Villa Park, Du Page Co., IL Contact: Mancini Peter (708) 584-2505

(3) UPGRADE OR REPAIR OF TANKS:

(a) ***Number and size of tanks being upgraded or repaired:*** (TK # 4) - 12,000 gallons, (TK # 5) - 10,000 gallons, (TK # 6) - 15,000 gallons

(b) ***Type of tanks:***

(c) ***Type of piping:*** **(TK # 4, 5, 6) - (Installing) partial Environ Geo Flex flexible double wall (see contingencies section). Contractor will be removing the far northeast ad the far northwest dispenser island, and he will replace these two islands / dispensers with 3 + 1 blender MPD's; consequently, the dispenser box will be "re-routed" to accommodate the new MPD's. Furthermore, there will be a small / partial amount of piping installed to accommodate this job. The partial sections will hook into the existing piping. It is unclear in our records whether the existing piping is single wall fiberglass or double wall fiberglass. The southwest island is going to be completely removed.**

(d) ***Product to be stored in each tank:*** (TK # 4) - Diesel Fuel, (TK # 5, 6) - Gasoline

(e) ***Type of leak detection being used:***

Tank:

Piping:

(f) ***Corrosion Protection being used:***

Tank:

Piping: **(TK # 4, 5, 6) - (Installing) partial non-corrosive flexible**

(g) ***Spill containment devices:***

(h) ***Overfill prevention devices:***

(i) ***Manway accessible at grade:***

(4) The owner must notify this Office when completion of tank upgrade/repair has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for underground piping upgrade, leak detection, spill and overfill prevention to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.

(5) SPECIAL CONTINGENCIES:

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Contact Person: Steve Tuttle
Phone:

Contractor Registration # Exp.

Sincerely,

Jim Coffey

cc: Storage Tank Safety Specialist -

Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)