



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 4025704
Permit # 00427-2023INS
Request Rec'd 04/24/2023
Amended Date
Approval Date 4/24/2023 DS
Permit Expires 10/24/2023

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Champaign Urbana Mass Trans Dist 803 E University Ave Urbana, IL 61801 Contact: David Thornton (217) 384-1144	(2) FACILITY - name and address where tanks are located: Champaign Urbana Mass Trans Dist 803 E University Ave Urbana, IL 61801 Contact: Dan Prutsman (217) 384-8188
---	---

(3) INSTALLATION OF TANKS:

- (a) *Number and size of tanks being installed: (TK # 7, 8) - 15,000*
- (b) *Type of tank(s): (TK # 7, 8) Tank - Fiberglass Double Wall KBK Industries*
- (c) *Type of piping: (TK # 7, 8) Piping - Fiberglass Double Wall Ameron Dualoy 3000/LCX from tanks to dispensers as shown in site plan, (TK # 7, 8) Piping - Double Wall STP/Tanktop Sump*
- (d) *Product to be stored in each tank: (TK # 7, 8) - Diesel Fuel*
- (e) *Type of leak detection being used:*
 - Tank: (TK # 7, 8) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 Plus , (TK # 7, 8) Leak Detect - Tank - Non-Discriminating Interstitial Monitoring Sensors With Monitor*
 - Piping: (TK # 7, 8) Leak Detect - Piping - Electronic Pressurized Line Leak Detection, (TK # 7, 8) Leak Detect - Piping - Non-Discriminating Sump Sensor with positive shutdown in all submersible and dispenser sumps, (TK # 7, 8) Leak Detect - Piping - Siphon Bar*
- (f) *Corrosion Protection being used:*
 - Tank: (TK # 7, 8) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 7, 8) Corrosion Prot - Piping - Fiberglass Non-Corrosive*
- (g) *Spill containment devices, piping and dispenser containment devices: (TK # 7, 8) Spill Contain Device - Double Wall Spill Bucket*
- (h) *Overfill prevention devices: (TK # 7, 8) Overfill Prev Device - Overfill Drop Tube Valve , (TK # 7, 8) Overfill Prev Device - Overfill Alarm*

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.
- (5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.
- (6) **SPECIAL CONTINGENCIES** : Will be removing Tank 5 & Tank 6 on the removal permit already applied for. Will install 2 new 15,000 gallon DW fiberglass diesel tanks. Install new equipment on both tanks. Run new piping from tanks to existing fuel islands/existing dispensers.


Install new TLS-450 Plus tank monitor. New sensors and probes installed. Purge, test and ensure proper installation before the OSFM IL Final.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Illinois Oil Marketing Equipment, Inc.
850 Brenkman Drive
Pekin, IL 61554

Contact Person: Bryan Estes
Phone: (309) 347-1819
Contractor Registration # IL1293 Exp. 2/4/2024

Sincerely,

A handwritten signature in cursive script that reads "Daniel G. Starks". The signature is written in dark ink and is positioned above a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist
Division File