



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov  
**Revised**

**FOR OFFICE USE ONLY**

Facility #: 2025054  
Permit #: 00705-2023INS  
Request Rec'd: 06/05/2023  
Approval Date: 06/27/2023 DS  
Extension Date: 06/27/2023  
Permit Expires: 12/27/2023

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

|                                                                                                                                                                                                        |                                                                                                                                                                                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>OWNER OF TANKS</b><br>- Corporation, partnership, or other business entity:<br>Soufian Abdelkader<br>8458 S. Cicero<br>Burbank, IL 60459<br>Cook County<br>Contact: Soufian Abdelkader 773/406-1600 | <b>FACILITY</b><br>- name and address where tanks are located:<br>Citgo Gas<br>1336 W. 127th St.<br>Calumet Park, IL 60827<br>Cook County<br>Contact: Abdallah Judeh 773/406-1600 |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**Tanks on the Permit**

| Tank # | Product            | Capacity | Tank Status        | Regulated Status |
|--------|--------------------|----------|--------------------|------------------|
| 7      | Gasoline - Regular | 10,000   | Tank Not Installed | Federal          |
| 8      | Gasoline - Premium | 4,000    | Tank Not Installed | Federal          |
| 9      | E-85               | 4,000    | Tank Not Installed | Federal          |

**Tank 7 Equipment**

| Equipment Type                | Permit Equipment                                      | Action |
|-------------------------------|-------------------------------------------------------|--------|
| Spill Containment Device      | Double Wall Spill Bucket                              | New    |
| Leak Detection - Tank         | Automatic Tank Gauging Red Jacket Pro Max             | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection            | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                              | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                              | New    |
| Corrosion Protection - Piping | Flexible Non-Corrosive                                | New    |
| Tank                          | Fiberglass Double Wall XERXES                         | New    |
| Piping                        | Flexible Double Wall NUPI Smartflex                   | New    |
| Piping                        | Single Wall STP/Tanktop Sump                          | New    |
| ➡ Leak Detection - Piping     | Non-Discriminating Sump Sensor with positive shutdown | New    |
| Leak Detection - Tank         | Non-Discriminating Interstitial Monitoring Sensors    | New    |

## Tank 8 Equipment

| Equipment Type                   | Permit Equipment                                      | Action |
|----------------------------------|-------------------------------------------------------|--------|
| Spill Containment Device         | Double Wall Spill Bucket                              | New    |
| Leak Detection - Piping          | Electronic Pressurized Line Leak Detection            | New    |
| Tank                             | Fiberglass Double Wall XERXES                         | New    |
| Leak Detection - Tank            | Automatic Tank Gauging Red Jacket Pro Max             | New    |
| Leak Detection - Tank            | Non-Discriminating Interstitial Monitoring Sensors    | New    |
| Piping                           | Single Wall STP/Tanktop Sump                          | New    |
| ↳ <i>Leak Detection - Piping</i> | Non-Discriminating Sump Sensor with positive shutdown | New    |
| Piping                           | Flexible Double Wall NUPI Smartflex                   | New    |
| Corrosion Protection - Piping    | Flexible Non-Corrosive                                | New    |
| Overfill Prevention Device       | Overfill Drop Tube Valve                              | New    |
| Corrosion Protection - Tank      | Fiberglass Non-Corrosive                              | New    |

## Tank 9 Equipment

| Equipment Type                   | Permit Equipment                                      | Action |
|----------------------------------|-------------------------------------------------------|--------|
| Spill Containment Device         | Double Wall Spill Bucket                              | New    |
| Leak Detection - Piping          | Electronic Pressurized Line Leak Detection            | New    |
| Tank                             | Fiberglass Double Wall XERXES                         | New    |
| Leak Detection - Tank            | Automatic Tank Gauging Red Jacket Pro Max             | New    |
| Leak Detection - Tank            | Non-Discriminating Interstitial Monitoring Sensors    | New    |
| Piping                           | Single Wall STP/Tanktop Sump                          | New    |
| ↳ <i>Leak Detection - Piping</i> | Non-Discriminating Sump Sensor with positive shutdown | New    |
| Piping                           | Flexible Double Wall NUPI Smartflex                   | New    |
| Corrosion Protection - Piping    | Flexible Non-Corrosive                                | New    |
| Overfill Prevention Device       | Overfill Drop Tube Valve                              | New    |
| Corrosion Protection - Tank      | Fiberglass Non-Corrosive                              | New    |

## Dispensers on the Permit

| Dispenser | Action                  |
|-----------|-------------------------|
| 1/2       | Sump / Sensors Changing |
| 3/4       | Sump / Sensors Changing |
| 5/6       | Sump / Sensors Changing |
| 7/8       | Sump / Sensors Changing |

## Dispenser 1/2 Equipment

| Equipment Type                   | Permit Equipment                                      | Action |
|----------------------------------|-------------------------------------------------------|--------|
| Dispenser                        | Single Wall UDC Sump                                  | New    |
| ↳ <i>Leak Detection - Piping</i> | Non-Discriminating Sump Sensor with positive shutdown | New    |

## Dispenser 3/4 Equipment

| Equipment Type                   | Permit Equipment                                      | Action |
|----------------------------------|-------------------------------------------------------|--------|
| Dispenser                        | Single Wall UDC Sump                                  | New    |
| ↳ <i>Leak Detection - Piping</i> | Non-Discriminating Sump Sensor with positive shutdown | New    |

**Dispenser 5/6 Equipment**

| Equipment Type            | Permit Equipment                                      | Action |
|---------------------------|-------------------------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump                                  | New    |
| ↳ Leak Detection - Piping | Non-Discriminating Sump Sensor with positive shutdown | New    |

**Dispenser 7/8 Equipment**

| Equipment Type            | Permit Equipment                                      | Action |
|---------------------------|-------------------------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump                                  | New    |
| ↳ Leak Detection - Piping | Non-Discriminating Sump Sensor with positive shutdown | New    |

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**

Instaling 2 new tanks double wall 4 islands same location

**Special Contingencies****Revision Reason:**

Changed to double wall spill buckets

**PERSON, FIRM OR COMPANY PERFORMING WORK:**

CAT Builders USA, Inc.  
522 E. Dundee Road  
Palatine, IL 60074

Contact Person: Jan kopytek  
Phone: 630/670-6280  
Email: Jankopytek@gmail.com  
Contractor License # IL002381 Exp. 5/6/2024

Sincerely,



Daniel Starks

**For Office Use Only****Dispenser 1/2 Equipment**

| Equipment Type | Permit Equipment       | Action   |
|----------------|------------------------|----------|
| Dispenser      | Not Installed UDC Sump | Removing |

**Dispenser 3/4 Equipment**

| Equipment Type | Permit Equipment       | Action   |
|----------------|------------------------|----------|
| Dispenser      | Not Installed UDC Sump | Removing |

**Dispenser 5/6 Equipment**

| Equipment Type | Permit Equipment       | Action   |
|----------------|------------------------|----------|
| Dispenser      | Not Installed UDC Sump | Removing |

**Dispenser 7/8 Equipment**

| Equipment Type | Permit Equipment       | Action   |
|----------------|------------------------|----------|
| Dispenser      | Not Installed UDC Sump | Removing |