



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY

Facility #: 1005442
Permit #: 01099-2023INS
Request Rec'd: 09/25/2023
Approval Date: 09/25/2023 DS
Permit Expires: 03/26/2024

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

| | |
|---|---|
| OWNER OF TANKS - Corporation, partnership, or other business entity: Woodhaven Association P.O. Box 110 509 Lamoille Road Sublette, IL 61367 Lee County Contact: Reece Howell 815/849-5107 | FACILITY - name and address where tanks are located: Woody's True Value 1802 Sublette (Lamoille & Tower Rd) Sublette, IL 61367 Lee County Contact: Scott Hanson 815/849-5107 |
|---|---|

Tanks on the Permit

| Tank # | Product | Capacity | Tank Status | Regulated Status |
|--------|--------------------|----------|--------------------|------------------|
| 6 | Gasoline - Regular | 12,000 | Tank Not Installed | Federal |
| 7 | Gasoline - Premium | 6,000 | Tank Not Installed | Federal |

Tank 6 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Corrosion Protection - Tank | Composite Non-Corrosive | New |
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Tank | Composite Double Wall Glasteel II | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P175SC | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Tank 7 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Corrosion Protection - Tank | Composite Non-Corrosive | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P175SC | New |
| Tank | Composite Double Wall Glasteel II | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Spill Containment Device | Double Wall Spill Bucket | New |

Dispensers on the Permit

| Dispenser | Action |
|-----------|-------------------------|
| 1/2 | Sump / Sensors Changing |
| 3/4 | Sump / Sensors Changing |
| 5/6 | Sump / Sensors Changing |
| 7/8 | Sump / Sensors Changing |

Dispenser 1/2 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 3/4 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 5/6 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 7/8 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Removing existing gasoline tanks (Diesel tank remains) Installing a new Modern Welding 18,000 gallon tank split 12/6 for the 2 gas products, replacing all piping at location. Will submit upgrade permit app for the diesel lines/sensors.

Special Contingencies


NOTE: Dispensers must be a full 10' from all buildings and property lines.

PERSON, FIRM OR COMPANY PERFORMING WORK:

Seneca Companies, Inc.
4140 East 14th Street PO Box 3360
Des Moines, IA 50313

Contact Person: Glen Davis
Phone: 563/340-5216
Email: gdavis@senecaco.com
Contractor License # IL598 Exp. 2/23/2024

Sincerely,



Daniel Starks

For Office Use Only**Dispenser 1/2 Equipment**

| Equipment Type | Permit Equipment | Action |
|----------------|------------------------|----------|
| Dispenser | Not Installed UDC Sump | Removing |

Dispenser 3/4 Equipment

| Equipment Type | Permit Equipment | Action |
|----------------|------------------------|----------|
| Dispenser | Not Installed UDC Sump | Removing |

Dispenser 5/6 Equipment

| Equipment Type | Permit Equipment | Action |
|----------------|------------------------|----------|
| Dispenser | Not Installed UDC Sump | Removing |

Dispenser 7/8 Equipment

| Equipment Type | Permit Equipment | Action |
|----------------|------------------------|----------|
| Dispenser | Not Installed UDC Sump | Removing |