



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov

**FOR OFFICE USE ONLY**

Facility #: 2030733  
Permit #: 01182-2023UPG  
Request Rec'd: 10/11/2023  
Approval Date: 10/12/2023 DS  
Permit Expires: 04/12/2024

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for  
Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: Chicago Nine Industrial Grant, LLC 29100 Northwestern Hwy., Suite 410 Southfield, MI 48034 (None) County Contact: Scott Harrison 248/457-9405	<b>FACILITY</b> - name and address where tanks are located: Power Solutions International 7850 S. Grant Street Burr Ridge, IL 60527 Du Page County Contact: Bob Riccardino 630/350-9400
---	---

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
3	Diesel Fuel	4,000	Currently in use	Federal
4	Gasoline - Regular	4,000	Currently in use	Federal

**Tank 3 Equipment**

Equipment Type	Permit Equipment	Action
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket

**Tank 4 Equipment**

Equipment Type	Permit Equipment	Action
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket

**Summary of Work**

Sawcut. remove and dispose of concrete over tanks.  
Excavate and remove pea stone as required for work. Stockpile on site for reuse.  
Cut and remove upper portion of (2) tank sumps. Dispose of debris.  
Remove and retain overfill valves for reuse.  
Remove and dispose of (2) overspill manholes.  
Remove (2) submersible pumps with mechanical line leak detectors and dispose of.

**Furnish and install the following NEW equipment:**

New retrofit fiberglass sump top collars & watertight covers. No work on piping or penetrations is included  
(2) new 5 gallon double wall spill containers.  
Fill adapters and caps.  
Vapor adapter and cap (gasoline tank only).  
(2) FE Petro Submersible Pumps.  
(2) Mechanical line leak detectors.  
Reinstall overfill valves.  
Back fill work area with excavated pea gravel.

**Furnish new manholes:**

(2) 42" manholes.  
(2) 18" observation well manholes.


(2) 18" vent extractor manholes.  
(1) 12" Vapor adapter and cap (gasoline tank only).  
Form and pour concrete 4000 psi @ 8" thick wire and fibermesh reinforced.

**Special Contingencies**

**NOTE: MLLD and Sub pumps are being changed under like for like**

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Crowne Industries, Ltd. 651 S. Sutton Road #214 Streamwood, IL 60107	Contact Person: Robert Sumoski Phone: 630/201-4967 Email: bob@crownetank.com Contractor License # IL002345 Exp. 5/16/2024

Sincerely,

  
\_\_\_\_\_

Daniel Starks