

## Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 217/785-1020 www.sfm.illinois.gov SFM.DPCS@illinois.gov Amended FOR OFFICE USE ONLY

Facility #: 3026528
Permit #: 01203-2023UPG
Request Rec'd: 10/18/2023
Amended Date:10/31/2023 DS
Approval Date: 10/18/2023 DS
Permit Expires: 04/18/2024

# <u>Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for</u> <u>Petroleum and Hazardous Substances</u>

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

#### THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS

- Corporation, partnership, or other business entity:

AM PM 125, Inc.

1012 E. Broadway P.O. Box 855

Astoria, IL 61501 (None) County

Contact: Gopal Basnet 217/306-2920

**FACILITY** 

- name and address where tanks are located:

AM PM 125, Inc.

1012 East Broadway P.O. Box 93

Astoria, IL 61501 Fulton County

Contact: Everest Thapa 512/818-7199

#### **Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	6,000	Currently in use	Federal
2	Gasoline - Premium	4,000	Currently in use	Federal
3	Diesel Fuel	4,000	Currently in use	Federal

#### Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	Replacing - Piping - Fiberglass Single Wall Piping A.O. Smith
Piping	Single Wall STP/Tanktop Sump	New
<b>L</b> eak Detection - Piping	Sump Sensor with positive shutdown	New
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve

#### **Tank 2 Equipment**

<b>Equipment Type</b>	Permit Equipment	Action
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	Replacing - Piping - Fiberglass Single Wall Piping A.O. Smith
Piping	Single Wall STP/Tanktop Sump	New
<b>└</b> Leak Detection - Piping	Sump Sensor with positive shutdown	New
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve

#### **Tank 3 Equipment**

Equipment Type	Permit Equipment	Action
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	Replacing - Piping - Fiberglass Single Wall Piping A.O. Smith
Piping	Single Wall STP/Tanktop Sump	New
<b>└</b> Leak Detection - Piping	Sump Sensor with positive shutdown	New
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve

#### **Dispensers on the Permit**

Dispenser	Action
1/2	Sump / Sensors Changing
3/4	Sump / Sensors Changing

#### Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

#### **Dispenser 3/4 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

## **Summary of Work**

REMOVING EXISTING SINGLE WALL SPILL BUCKETS AND REPLACING WITH DOUBLEWALL SPILL BUCKET. SINGLE WALL SPILL BUCKETS FAILED INSPECTION

#### **Special Contingencies**

Replaced piping exceeds 20 feet or 50% of the total pipe run.

#### **Amendment Reason:**

REPIPE STATION AND INSTALL NEW SUMPS AND PIPE

PERSON, FIRM OR COMPANY PERFORMING WORK:		
R. L. Hoener Company 2923 Gardner Expressway P. O. Box 1086 Quincy, IL 62305	Contact Person: Marty Jackson Phone: 217/223-2190 Email: KMAJORS@RLHOENER.COM Contractor License # IL2021 Exp. 5/22/2024	



#### **Daniel Starks**

## For Office Use Only

## Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Piping	Not Installed STP/Tanktop Sump	Removing

## **Tank 2 Equipment**

Equipment Type	Permit Equipment	Action
Piping	Not Installed STP/Tanktop Sump	Removing

## Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Piping	Not Installed STP/Tanktop Sump	Removing

## Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

#### **Dispenser 3/4 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing