



**Office of the Illinois State Fire Marshal**  
**Division of Petroleum and Chemical Safety**  
 1035 Stevenson Drive  
 Springfield, IL 62703  
 217/785-1020  
 www.sfm.illinois.gov  
 SFM.DPCS@illinois.gov  
**Extended**

FOR OFFICE USE ONLY	
Facility #:	2022923
Permit #:	00676-2023INS
Request Rec'd:	06/20/2023
Approval Date:	06/21/2023 DS
Extension Date:	10/31/2023
Permit Expires:	06/21/2024

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE EXTENSION DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity:  Lucky Location, Inc. 13604 S. Archer Ave. Lemont, IL 60439 (None) County  Contact: Paramvir Singh 641/275-2103	<b>FACILITY</b> - name and address where tanks are located:  Lucky Location, Inc. 11458 S. Cicero Alsip, IL 60803 Cook County  Contact: Samera Ramahi 641/275-2103
---	--

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
4	Gasoline - Regular	18,000	Installed/Not in Use	Federal
5	Gasoline - Premium	6,000	Installed/Not in Use	Federal
6	Diesel Fuel	6,000	Installed/Not in Use	Federal

**Tank 4 Equipment**

Equipment Type	Permit Equipment	Action
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Spill Containment Device	Double Wall Spill Bucket	New
Overfill Prevention Device	Overfill Alarm	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Tank	Fiberglass Double Wall XERXES	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Ball Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Tank	Fiberglass Double Wall XERXES	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
↳ <i>Leak Detection - Piping</i>	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

### Tank 6 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Tank	Fiberglass Double Wall XERXES	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
↳ <i>Leak Detection - Piping</i>	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

### Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New
9/10	New
11/12	New

### Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ <i>Leak Detection - Piping</i>	Sump Sensor with positive shutdown	New

**Dispenser 3/4 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 5/6 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 7/8 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 9/10 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 11/12 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**

Installation of a 30,000-gallon Xerxes double-wall fiberglass triple compartment tank split 6/18/6 with new tank top equipment, leak detection, and double-wall pipe to six new dispensers.

**Special Contingencies**

PERSON, FIRM OR COMPANY PERFORMING WORK:	
B & K Equipment Company 2939 175th Street Lansing, IL 60438	Contact Person: Ed Angell Phone: 708/474-3344 Email: jim.veverka@bkequip.com Contractor License # IL1207 Exp. 2/14/2024

Sincerely,



Daniel Starks