



**Office of the Illinois State Fire Marshal**  
**Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov  
**Revised**

**FOR OFFICE USE ONLY**

Facility #: 1005442  
Permit #: 01100-2023UPG  
Request Rec'd: 09/25/2023  
Approval Date: 09/25/2023 DS  
Extension Date: 11/22/2023  
Permit Expires: 03/26/2024

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: Woodhaven Association P.O. Box 110 509 Lamoille Road Sublette, IL 61367 Lee County Contact: Scott Hanson 815/849-5107	<b>FACILITY</b> - name and address where tanks are located: Woody's True Value 1802 Sublette (Lamoille & Tower Rd) Sublette, IL 61367 Lee County Contact: Scott Hanson 815/849-5107
---	---

**Tanks on the Permit For Piping Only**

Tank #	Product	Capacity	Tank Status	Regulated Status
5	Diesel Fuel	5,000	Currently in use	Federal

**Tank 5 Equipment**

Equipment Type	Permit Equipment	Action
Piping	Flexible Double Wall A.P.T. Poly Tech P175SC	Replacing - Piping - Fiberglass Double Wall
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	Replacing - Leak Detect - Piping - Mechanical Pressurized Line Leak Detection
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket
Corrosion Protection - Piping	Flexible Non-Corrosive	Replacing - Corrosion Prot - Piping - Fiberglass Non-Corrosive
Corrosion Protection - Piping	Isolation Boots Flex Connector	Removing
Corrosion Protection - Piping	Sacrificial Anode Cathodic Protection	Removing
Piping	Single Wall STP/Tanktop Sump	Replacing - Piping - Single Wall STP/Tanktop Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 with CSLD	Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350

**Summary of Work**

Replace existing diesel line with new flexible APT piping, add sensor to the diesel STP sump and add ELLD to the diesel line.

**Special Contingencies**

Replaced piping exceeds 20 feet or 50% of the total pipe run.

**Amendment Reason:**

Had to replace the Diesel STP Sump, existing would not pass a hydro test  
Replaced piping exceeds 20 feet or 50% of the total pipe run.

**Amendment Reason:**


Had to replace the Diesel STP Sump, existing would not pass a hydro test Need to add the TLS 450Plus to Tank #5

**Revision Reason:**

Contractor needed the TLS450 with CSLD added

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Seneca Companies, Inc. 4140 East 14th Street PO Box 3360 Des Moines, IA 50313	Contact Person: Glen Davis Phone: 563/340-5216 Email: gdavis@senecaco.com Contractor License # IL598 Exp. 2/23/2024

Sincerely,



Daniel Starks