



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 2047734
Permit #: 00387-2024INS
Request Rec'd: 04/04/2024
Approval Date: 04/08/2024 DS
Permit Expires: 10/08/2024

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

| | |
|---|---|
| OWNER OF TANKS - Corporation, partnership, or other business entity: OM Group 200 S. Frontage Road Burr Ridge, IL 60527 Contact: Kalpesh Patel 630/568-3240 | FACILITY - name and address where tanks are located: Speed Trek Joliet 2565 PLAINFIELD ROAD Joliet, IL 60435 Will County Contact: Patel 630/568-3240 |
|---|---|

Tanks on the Permit

| Tank # | Product | Capacity | Tank Status | Regulated Status |
|--------|--------------------|----------|--------------------|------------------|
| 1 | Gasoline - Regular | 20,000 | Tank Not Installed | Federal |
| 2 | Gasoline - Premium | 8,000 | Tank Not Installed | Federal |
| 3 | Diesel Fuel | 12,000 | Tank Not Installed | Federal |

Tank 1 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Overfill Prevention Device | Overfill Alarm | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Tank | Fiberglass Double Wall XERXES | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P150SC | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Piping | Other Submersible Pump | New |
| Piping | Shear Valves | New |
| Piping | Ball Valves | New |

Tank 2 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Overfill Prevention Device | Overfill Alarm | New |
| Tank | Fiberglass Double Wall XERXES | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P150SC | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Piping | Other Submersible Pump | New |
| Piping | Ball Valves | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Tank 3 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Overfill Prevention Device | Overfill Alarm | New |
| Tank | Fiberglass Double Wall XERXES | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P200SC | New |
| Piping | Other Submersible Pump | New |
| Piping | Ball Valves | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispensers on the Permit

| Dispenser | Action |
|-----------|--------|
| 1/2 | New |
| 3/4 | New |
| 5/6 | New |
| 7/8 | New |
| 9/10 | New |
| 11/12 | New |
| 13/14 | New |
| 15/16 | New |
| Master 17 | New |
| Master 18 | New |
| Satellite | New |

Dispenser 1/2 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 3/4 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 5/6 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 7/8 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 9/10 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 11/12 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 13/14 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 15/16 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser Master 17 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser Master 18 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser Satellite Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Installation of a 28,000-gallon compartment tank split 20/8, and a 12,000-gallon tank. Eight gasoline dispensers and three truck diesel dispensers.

Special Contingencies

| PERSON, FIRM OR COMPANY PERFORMING WORK: | |
|---|--|
| B & K Equipment Company 2939 175th Street Lansing, IL 60438 | Contact Person: Ed Angell Phone: 708/474-3344 Email: jim.veverka@bkequip.com Contractor License # IL1207 Exp. 2/14/2026 |

Sincerely,



Daniel Starks