



**Office of the Illinois State Fire Marshal**  
**Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov  
**Extended**

**FOR OFFICE USE ONLY**  
Facility #: 2006951  
Permit #: 01393-2023INS  
Request Rec'd: 11/09/2023  
Approval Date: 12/05/2023 DS  
Extension Date: 06/03/2024  
Permit Expires: 12/05/2024

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE EXTENSION DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: RDK Ventures, LLC 1100 Situs Court, Suite 100 Raleigh, NC 27606 Du Page County Contact: Elizabeth Sauser 708/748-3496	<b>FACILITY</b> - name and address where tanks are located: Circle K #6702 2210 West 22nd Street Oak Brook, IL 60522 Du Page County Contact: Maria Rodriguez 630/586-0205
---	---


**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
4	Gasoline - Regular	20,000	Installed/Not in Use	Federal
5	Gasoline - Premium	12,000	Installed/Not in Use	Federal
6	Diesel Fuel	12,000	Installed/Not in Use	Federal
7	Gasoline - Regular	8,000	Installed/Not in Use	Federal


**Tank 4 Equipment**

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Flexible Double Wall NUPI Smartflex	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Spill Containment Device	Double Wall Spill Bucket	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Tank	Fiberglass Double Wall Containment Solutions	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall NUPI Smartflex	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

## Tank 6 Equipment

Equipment Type	Permit Equipment	Action
Tank	Fiberglass Double Wall Containment Solutions	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall NUPI Smartflex	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

## Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Tank	Fiberglass Double Wall Containment Solutions	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall NUPI Smartflex	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

## Dispensers on the Permit

Dispenser	Action
1/2	Sump / Sensors Changing
3/4	Sump / Sensors Changing
5/6	Sump / Sensors Changing
7/8	Sump / Sensors Changing
9/10	Sump / Sensors Changing
11/12	Sump / Sensors Changing
13/14	Sump / Sensors Changing
15/16	Sump / Sensors Changing

## Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor

## Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor

## Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor

## Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor with positive shutdown

### Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor

### Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor

### Dispenser 13/14 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor

### Dispenser 15/16 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
Leak Detection - Piping	Sump Sensor with positive shutdown	Replacing - Leak Detect - Piping - Sump Sensor

### General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

### Summary of Work

#### TANKS:

- (1) 20,000 gallon 10' dia. double wall fiberglass tank (Regular)
- (1) 20,000 gallon 10' dia. double wall fiberglass tank, split 12/8. (Prem/Reg)
- (1) 12,000 gallon 8' dia. double wall fiberglass tank, split 12/8. (Diesel)

Concrete dead men hold downs, straps & turnbuckles.

#### OVERSPILL/OVERFILL PREVENTION:

- (4) 5 gallon, below-grade level overspill containment manholes.
- (4) OPW overfill drop tubes.

#### SUMPS:

- (4) 42" fiberglass water-tight piping sumps at tank tops.
- (8) Fiberglass under dispenser sumps at islands

#### PIPING:

2" Double wall UL approved flexible pipe system.  
Ameron single wall fiberglass vent piping system.

#### SUBMERSIBLE PUMPS:

- (1) FE Petro 4 HP variable speed submersible pumps with Electronic Line Leak Detector
- (3) FE Petro 2 HP submersible pump with Electronic Line Leak Detector
- (4) Pump controllers.

#### LEAK DETECTION:

- (1) Veeder-Root TLS-450 monitor console.
- (4) Tank level probes.
- (3) Tank interstitial sensors.
- (8) Dispenser sump sensors.
- (4) Tank sump sensors.
- (4) Digital Pressurized line leak detectors.

### Special Contingencies

**PERSON, FIRM OR COMPANY PERFORMING WORK:**

Crowne Industries, Ltd.  
651 S. Sutton Road #214  
Streamwood, IL 60107

Contact Person: Robert Sumoski  
Phone: 630/201-4967  
Email: bob@crownetank.com  
Contractor License # IL002345 Exp. 5/16/2024

Sincerely,



---

Daniel Starks