



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov  
**Amended**

|                            |               |
|----------------------------|---------------|
| <b>FOR OFFICE USE ONLY</b> |               |
| Facility #:                | 2047753       |
| Permit #:                  | 00644-2024INS |
| Request Rec'd:             | 05/24/2024    |
| Approval Date:             | 05/28/2024 DS |
| Amended Date:              | 07/23/2024 DS |
| Permit Expires:            | 11/30/2024    |

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

|                                                                                                                                                                                                                       |                                                                                                                                                                                                                  |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>OWNER OF TANKS</b><br>- Corporation, partnership, or other business entity:<br>Lenny's Gas N Wash 65th & Central, LLC<br>8200 W 185th St. Unit K<br>Tinley Park, IL 60487<br>Contact: Leonard McEnery 708/444-0117 | <b>FACILITY</b><br>- name and address where tanks are located:<br>Lenny's Gas N Wash 65th & Central, LLC<br>5611 W 65th Street<br>Bedford Park, IL 60638<br>Cook County<br>Contact: Leonard McEnery 708/444-0117 |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**Tanks on the Permit**

| Tank # | Product            | Capacity | Tank Status        | Regulated Status |
|--------|--------------------|----------|--------------------|------------------|
| 1      | Gasoline - Regular | 20,000   | Tank Not Installed | Federal          |
| 2      | Gasoline - Premium | 6,000    | Tank Not Installed | Federal          |
| 3      | E85                | 10,000   | Tank Not Installed | Federal          |
| 4      | Diesel Fuel        | 6,000    | Tank Not Installed | Federal          |
| 5      | Diesel Fuel        | 20,000   | Tank Not Installed | Federal          |

## Tank 1 Equipment

| Equipment Type                                                                                            | Permit Equipment                                                | Action |
|-----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|--------|
| Leak Detection - Tank                                                                                     | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD       | New    |
| Leak Detection - Tank                                                                                     | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New    |
| Leak Detection - Piping                                                                                   | Electronic Pressurized Line Leak Detection                      | New    |
| Spill Containment Device                                                                                  | Double Wall Spill Bucket                                        | New    |
| Overfill Prevention Device                                                                                | Overfill Drop Tube Valve                                        | New    |
| Corrosion Protection - Tank                                                                               | Fiberglass Non-Corrosive                                        | New    |
| Corrosion Protection - Piping                                                                             | Fiberglass Non-Corrosive                                        | New    |
| Tank                                                                                                      | Fiberglass Double Wall XERXES                                   | New    |
| Piping                                                                                                    | Fiberglass Double Wall Ameron Dualoy 3000/LCX                   | New    |
| Piping                                                                                                    | Other Steel Riser                                               | New    |
| Piping                                                                                                    | Other Submersible Pump                                          | New    |
| Piping                                                                                                    | Flex Connector Steel                                            | New    |
| Piping                                                                                                    | Single Wall STP/Tanktop Sump                                    | New    |
|  Leak Detection - Piping | Sump Sensor with positive shutdown                              | New    |
| Piping                                                                                                    | Ball Valves                                                     | New    |
| Piping                                                                                                    | Shear Valves                                                    | New    |

## Tank 2 Equipment

| Equipment Type                                                                                              | Permit Equipment                                                | Action |
|-------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|--------|
| Leak Detection - Tank                                                                                       | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New    |
| Leak Detection - Piping                                                                                     | Electronic Pressurized Line Leak Detection                      | New    |
| Tank                                                                                                        | Fiberglass Double Wall XERXES                                   | New    |
| Piping                                                                                                      | Fiberglass Double Wall Ameron Dualoy 3000/LCX                   | New    |
| Leak Detection - Tank                                                                                       | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD       | New    |
| Piping                                                                                                      | Ball Valves                                                     | New    |
| Corrosion Protection - Piping                                                                               | Fiberglass Non-Corrosive                                        | New    |
| Piping                                                                                                      | Other Submersible Pump                                          | New    |
| Piping                                                                                                      | Single Wall STP/Tanktop Sump                                    | New    |
|  Leak Detection - Piping | Sump Sensor with positive shutdown                              | New    |
| Piping                                                                                                      | Other Steel Riser                                               | New    |
| Piping                                                                                                      | Flex Connector Steel                                            | New    |
| Overfill Prevention Device                                                                                  | Overfill Drop Tube Valve                                        | New    |
| Corrosion Protection - Tank                                                                                 | Fiberglass Non-Corrosive                                        | New    |
| Piping                                                                                                      | Shear Valves                                                    | New    |
| Spill Containment Device                                                                                    | Double Wall Spill Bucket                                        | New    |

### Tank 3 Equipment

| Equipment Type                | Permit Equipment                                                | Action |
|-------------------------------|-----------------------------------------------------------------|--------|
| Leak Detection - Tank         | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                      | New    |
| Tank                          | Fiberglass Double Wall XERXES                                   | New    |
| Piping                        | Fiberglass Double Wall Ameron Dualoy 3000/LCX                   | New    |
| Leak Detection - Tank         | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD       | New    |
| Piping                        | Ball Valves                                                     | New    |
| Corrosion Protection - Piping | Fiberglass Non-Corrosive                                        | New    |
| Piping                        | Other Submersible Pump                                          | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                    | New    |
| 🔧 Leak Detection - Piping     | Sump Sensor with positive shutdown                              | New    |
| Piping                        | Other Steel Riser                                               | New    |
| Piping                        | Flex Connector Steel                                            | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                        | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                        | New    |
| Piping                        | Shear Valves                                                    | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                        | New    |

### Tank 4 Equipment

| Equipment Type                | Permit Equipment                                                | Action |
|-------------------------------|-----------------------------------------------------------------|--------|
| Leak Detection - Tank         | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                      | New    |
| Tank                          | Fiberglass Double Wall XERXES                                   | New    |
| Piping                        | Fiberglass Double Wall Ameron Dualoy 3000/LCX                   | New    |
| Leak Detection - Tank         | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD       | New    |
| Piping                        | Ball Valves                                                     | New    |
| Corrosion Protection - Piping | Fiberglass Non-Corrosive                                        | New    |
| Piping                        | Other Submersible Pump                                          | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                    | New    |
| 🔧 Leak Detection - Piping     | Sump Sensor with positive shutdown                              | New    |
| Piping                        | Other Steel Riser                                               | New    |
| Piping                        | Flex Connector Steel                                            | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                        | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                        | New    |
| Piping                        | Shear Valves                                                    | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                        | New    |

## Tank 5 Equipment

| Equipment Type                | Permit Equipment                                                | Action |
|-------------------------------|-----------------------------------------------------------------|--------|
| Leak Detection - Tank         | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                      | New    |
| Tank                          | Fiberglass Double Wall XERXES                                   | New    |
| Piping                        | Fiberglass Double Wall Ameron Dualoy 3000/LCX                   | New    |
| Leak Detection - Tank         | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD       | New    |
| Piping                        | Ball Valves                                                     | New    |
| Corrosion Protection - Piping | Fiberglass Non-Corrosive                                        | New    |
| Piping                        | Other Submersible Pump                                          | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                    | New    |
| 🔗 Leak Detection - Piping     | Sump Sensor with positive shutdown                              | New    |
| Piping                        | Other Steel Riser                                               | New    |
| Piping                        | Flex Connector Steel                                            | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                        | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                        | New    |
| Piping                        | Shear Valves                                                    | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                        | New    |

## Dispensers on the Permit

| Dispenser | Action |
|-----------|--------|
| 1/2       | New    |
| 3/4       | New    |
| 5/6       | New    |
| 7/8       | New    |
| 9/10      | New    |
| 11/12     | New    |
| 13/14     | New    |
| 15/16     | New    |
| 17/18     | New    |
| 19/20     | New    |
| 21/22     | New    |
| 23/24     | New    |
| 25/26     | New    |
| 27/28     | New    |
| 29M       | New    |
| 29S/30M   | New    |
| 30S/31M   | New    |
| 31S/32M   | New    |
| 32S       | New    |

## Dispenser 1/2 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔗 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 3/4 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 5/6 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 7/8 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 9/10 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 11/12 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 13/14 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 15/16 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 17/18 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 19/20 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 21/22 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 23/24 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 25/26 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 27/28 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 29M Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 29S/30M Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 30S/31M Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 31S/32M Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 32S Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**

Installing new station per the attached.

Customer shifted tanks away from property line. See new drawing. Everything else remains the same.

**Special Contingencies****Amendment Reason:**

Customer shifted tank location away from property line.

| PERSON, FIRM OR COMPANY PERFORMING WORK:                                   |                                                                                                                                      |
|----------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------|
| Anderson Pump Service, Inc.<br>19659 South 97th Avenue<br>Mokena, IL 60448 | Contact Person: Ron Anderson<br>Phone: 708/243-9081<br>Email: Steve@andersonpump.com<br>Contractor License # IL002275 Exp. 5/21/2026 |

Sincerely,



Daniel Starks