



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov
Amended

FOR OFFICE USE ONLY
Facility #: 2011434
Permit #: 00925-2024UPG
Request Rec'd: 08/04/2024
Approval Date: 08/05/2024 DS
Amended Date: 08/06/2024 DS
Permit Expires: 02/05/2025

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Peacock Oil Company 1470 Jarvis Avenue Elk Grove Village, IL 60007 Cook County Contact: Brian Cho 847/274-5886	FACILITY - name and address where tanks are located: S and S Energy, Inc. 1060 East Park Avenue Libertyville, IL 60048 Lake County Contact: Snehal Patel 847/362-6620
--	--

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Diesel Fuel	6,000	Currently in use	Federal
2	Gasoline - Regular	8,000	Currently in use	Federal
3	Gasoline - Premium	8,000	Currently in use	Federal
4	Gasoline - Regular	8,000	Currently in use	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Ball Float Vent Valve

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Ball Float Vent Valve
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket

Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Ball Only Removed Ball Float Vent Valve

Tank 4 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Ball Float Vent Valve
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket

Summary of Work

Dig down is needed on the tanks 2 and 3 to change the risers since drop tubes were stuck to the risers

All the NOV issues will be taken care as part of the this permit

Amendment:: Removing the ball floats from all the tanks vent lines as per the NOV requirement

Thank you

Innovative Constructions

Special Contingencies

Amendment Reason:


Tank 4 drop tube was stuck, not able to remove. Need to dig down to the tank top to change the riser Thank you Innovative Constructions

PERSON, FIRM OR COMPANY PERFORMING WORK:

Innovative Constructions Technology LLC
245 W Roosevelt Rd Building 4, Unit 28
West Chicago, IL 60185

Contact Person: Raju penumatsa
Phone: 630/747-3404
Email: iconstructions81@gmail.com
Contractor License # IL002453 Exp. 2/7/2026

Sincerely,



Daniel Starks