



**Office of the Illinois State Fire Marshal**  
**Division of Petroleum and Chemical Safety**  
 1035 Stevenson Drive  
 Springfield, IL 62703  
 217/785-1020  
 www.sfm.illinois.gov  
 SFM.DPCS@illinois.gov  
**Amended**

|                            |               |
|----------------------------|---------------|
| <b>FOR OFFICE USE ONLY</b> |               |
| Facility #:                | 4043622       |
| Permit #:                  | 00723-2024INS |
| Request Rec'd:             | 06/10/2024    |
| Approval Date:             | 06/13/2024 DS |
| Amended Date:              | 10/07/2024 DS |
| Permit Expires:            | 12/13/2024    |

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

|  |  |
|--|--|
| <b>OWNER OF TANKS</b><br>- Corporation, partnership, or other business entity:<br>Pilot Travel Centers, LLC<br>5508 Lonas Rd.<br>Knoxville, TN 37909<br>Knox County<br>Contact: Joey Cupp 865/588-7488 | <b>FACILITY</b><br>- name and address where tanks are located:<br>Pilot Travel Center #368<br>4030 E. Boyd Road<br>Decatur, IL 62526<br>Macon County<br>Contact: Leigh West 865/588-7488 |
|--|--|

**Tanks on the Permit**

| Tank # | Product     | Capacity | Tank Status          | Regulated Status |
|--------|-------------|----------|----------------------|------------------|
| 7      | Diesel Fuel | 30,000   | Installed/Not in Use | Federal          |
| 8      | Diesel Fuel | 30,000   | Installed/Not in Use | Federal          |
| 9      | B-99        | 30,000   | Installed/Not in Use | Federal          |

**Tank 7 Equipment**

| Equipment Type                | Permit Equipment                                   | Action |
|-------------------------------|--|--------|
| Overfill Prevention Device    | Overfill Drop Tube Valve                           | New    |
| Spill Containment Device      | Double Wall Spill Bucket                           | New    |
| Leak Detection - Piping       | Mechanical Pressurized Line Leak Detection         | New    |
| Leak Detection - Tank         | Automatic Tank Gauging Veeder Root TLS 350         | New    |
| Tank                          | Fiberglass Double Wall XERXES                      | New    |
| Piping                        | Fiberglass Double Wall Ameron Dualoy 3000/LCX      | New    |
| Piping                        | Flex Connector Steel                               | New    |
| Piping                        | Double Wall Transition Sump                        | New    |
| ↳ Leak Detection - Piping     | Sump Sensor with positive shutdown                 | New    |
| Piping                        | Ball Valves  | New    |
| Corrosion Protection - Piping | Fiberglass Non-Corrosive                           | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                           | New    |
| Leak Detection - Tank         | Non-Discriminating Interstitial Monitoring Sensors | New    |
| Piping                        | Single Wall STP/Tanktop Sump                       | New    |
| ↳ Leak Detection - Piping     | Sump Sensor with positive shutdown                 | New    |

## Tank 8 Equipment

| Equipment Type                | Permit Equipment                                   | Action |
|-------------------------------|--|--------|
| Tank                          | Fiberglass Double Wall XERXES                      | New    |
| Piping                        | Fiberglass Double Wall Ameron Dualoy 3000/LCX      | New    |
| Piping                        | Flex Connector Steel                               | New    |
| Piping                        | Double Wall Transition Sump                        | New    |
| ↳ Leak Detection - Piping     | Sump Sensor with positive shutdown                 | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                           | New    |
| Leak Detection - Tank         | Automatic Tank Gauging Veeder Root TLS 350         | New    |
| Spill Containment Device      | Double Wall Spill Bucket                           | New    |
| Piping                        | Ball Valves  | New    |
| Leak Detection - Piping       | Mechanical Pressurized Line Leak Detection         | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                           | New    |
| Corrosion Protection - Piping | Fiberglass Non-Corrosive                           | New    |
| Leak Detection - Tank         | Non-Discriminating Interstitial Monitoring Sensors | New    |
| Piping                        | Single Wall STP/Tanktop Sump                       | New    |
| ↳ Leak Detection - Piping     | Sump Sensor with positive shutdown                 | New    |

## Tank 9 Equipment

| Equipment Type                | Permit Equipment                                   | Action |
|-------------------------------|--|--------|
| Piping                        | Fiberglass Double Wall Ameron Dualoy 3000/LCX      | New    |
| Leak Detection - Tank         | Automatic Tank Gauging Veeder Root TLS 350         | New    |
| Spill Containment Device      | Double Wall Spill Bucket                           | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                           | New    |
| Tank                          | Fiberglass Double Wall XERXES                      | New    |
| Piping                        | Other Steel Riser                                  | New    |
| Leak Detection - Piping       | American with Sensors/No Test Suction              | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                           | New    |
| Corrosion Protection - Piping | Fiberglass Non-Corrosive                           | New    |
| Leak Detection - Tank         | Non-Discriminating Interstitial Monitoring Sensors | New    |
| Piping                        | Single Wall STP/Tanktop Sump                       | New    |
| ↳ Leak Detection - Piping     | Sump Sensor with positive shutdown                 | New    |

## Dispensers on the Permit

| Dispenser | Action |
|-----------|--------|
| B99       | New    |

## Dispenser B99 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


**Special Contingencies**

**Amendment Reason:**

ADDING GASBOY DISPENSER WITH BENECORE HEAT

| PERSON, FIRM OR COMPANY PERFORMING WORK:                                       |   |
|--|---|
| Neumayer Equipment Company, Inc.<br>5060 Arsenal Street<br>St. Louis, MO 63139 | Contact Person: Jimmy Spiros<br>Phone: 314/772-4501<br>Email: testing@neumayerequipment.com<br>Contractor License # IL1502 Exp. 3/26/2026 |

Sincerely,

  
\_\_\_\_\_

Daniel Starks