



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
 1035 Stevenson Drive
 Springfield, IL 62703
 217/785-1020
 www.sfm.illinois.gov
 SFM.DPCS@illinois.gov
Amended

FOR OFFICE USE ONLY	
Facility #:	2021642
Permit #:	01075-2024INS
Request Rec'd:	09/03/2024
Approval Date:	09/04/2024 DS
Amended Date:	10/21/2024 DS
Permit Expires:	03/05/2025

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Laila Enterprises, Inc. 2013 Sibley Blvd. Calumet City, IL 60409 Cook County Contact: Sohail Khan 708/891-4645	FACILITY - name and address where tanks are located: Cal City Citgo 2013 Sibley Blvd. Calumet City, IL 60409 Cook County Contact: Sobail Khan 708/891-4645
--	---

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
6	Gasoline - Regular	12,000	Installed/Not in Use	Federal
7	Gasoline - Premium	4,000	Installed/Not in Use	Federal
8	B-11	4,000	Installed/Not in Use	Federal
9	E85	4,000	Installed/Not in Use	Federal

Tank 6 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Spill Containment Device	Double Wall Spill Bucket	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Tank	Composite Double Wall Glasteel II	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Piping	Single Wall STP/Tanktop Sump	New
👉 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Shear Valves	New
Piping	Flex Connector Steel	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New

Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Tank	Composite Double Wall Glasteel II	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

Tank 8 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Tank	Composite Double Wall Glasteel II	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

Tank 9 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Tank	Composite Double Wall Glasteel II	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

Dispensers on the Permit

Dispenser	Action
1/2	Sump / Sensors Changing
3/4	Sump / Sensors Changing
5/6	Sump / Sensors Changing
7/8	Sump / Sensors Changing

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Installing 2 new tanks, 4 UDC and all new sensors and probes


Special Contingencies

Amendment Reason:

Updating Piping layout

PERSON, FIRM OR COMPANY PERFORMING WORK:	
America Petropump Services LLC d/b/a Ampsco Services 4075 Fox Valley Center Dr., Unit 9 Aurora, IL 60504	Contact Person: Ravindra Penmatsa Phone: 312/286-6722 Email: ravi@ampsco.net Contractor License # IL002420 Exp. 5/22/2025

Sincerely,



Daniel Starks

For Office Use Only		
Dispenser 1/2 Equipment		
Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing
Dispenser 3/4 Equipment		
Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing
Dispenser 5/6 Equipment		
Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing
Dispenser 7/8 Equipment		
Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing