



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 6047636
Permit #: 01371-2024INS
Request Rec'd: 10/23/2024
Approval Date: 10/28/2024 DS
Permit Expires: 04/29/2025

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Ravinder K. Tut 10 Winged Foot Dr. Highland, IL 62249 Contact: Sunny Tut 209/610-1313	FACILITY - name and address where tanks are located: Paragpur Travel Center 450 Robinson Cemetery Ave Pocahontas, IL 62275 Bond County Contact: Sunny Tut 209/610-1313
--	---


Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Premium	4,000	Installed/Not in Use	Federal
2	Gasoline - Regular	20,000	Installed/Not in Use	Federal
3	Gasoline - Non Ethanol	6,000	Installed/Not in Use	Federal
4	Diesel Fuel	10,000	Installed/Not in Use	Federal
5	Diesel Fuel	10,000	Installed/Not in Use	Federal
6	Diesel Fuel	30,000	Installed/Not in Use	Federal


Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Spill Containment Device	Double Wall Spill Bucket	New
Overfill Prevention Device	Overfill Alarm	New
Tank	Composite Double Wall Modern Welding Glasteel 1	New
Piping	Ball Valves	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall A.P.T. Poly Tech XP 1500	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Piping	Single Wall STP/Tanktop Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New


Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall A.P.T. Poly Tech XP 1500	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Tank	Composite Double Wall Modern Welding Glasteel 1	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Spill Containment Device	Double Wall Spill Bucket	New


Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall A.P.T. Poly Tech XP 1500	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Tank	Composite Double Wall Modern Welding Glasteel 1	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Spill Containment Device	Double Wall Spill Bucket	New


Tank 4 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall A.P.T. Poly Tech XP 1500	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Tank	Composite Double Wall Modern Welding Glasteel 1	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Spill Containment Device	Double Wall Spill Bucket	New

Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall A.P.T. Poly Tech XP 1500	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Tank	Composite Double Wall Modern Welding Glasteel 1	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Spill Containment Device	Double Wall Spill Bucket	New


Tank 6 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Piping	Ball Valves	New
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flexible Double Wall A.P.T. Poly Tech XP 1500	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Tank	Composite Double Wall Modern Welding Glasteel 1	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Spill Containment Device	Double Wall Spill Bucket	New


Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New
9/10	New
11/12	New
13/14	New
15/16	New
17 S	New
18 M/S	New
19 M/S	New
20 M/S	New
21 M/S	New
22 M	New

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 13/14 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 15/16 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 17 S Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 18 M/S Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 19 M/S Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 20 M/S Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔌 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 21 M/S Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔌 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 22 M Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔌 Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

another company started this install.


we are responsible for the dispensers, probes, sensors and pos.

Special Contingencies

NOTES: All dispensers must be a full 10' to buildings and property lines. Vents must meet section 175.440 of our rules

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Neumayer Equipment Company, Inc. 5060 Arsenal Street St. Louis, MO 63139	Contact Person: Jimmy Spiros Phone: 314/772-4501 Email: testing@neumayerequipment.com Contractor License # IL1502 Exp. 3/26/2026

Sincerely,



Daniel Starks