

Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety 1035 Stevenson Drive Springfield, IL 62703 217/785-1020 www.sfm.illinois.gov SFM.DPCS@illinois.gov

 FOR OFFICE USE ONLY

 Facility #:
 2047843

 Permit #:
 01571-2024INS

 Request Rec'd:
 12/04/2024

 Approval Date:
 12/05/2024 DS

 Permit Expires:
 06/05/2025

## Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: https://webapps.sfm.illinois.gov/USTPortal/NotificationForm.

## THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS	FACILITY
- Corporation, partnership, or other business entity:	- name and address where tanks are located:
City of Aurora	City of Aurora Public Works
44 E. Downer Place P.O. Box 2067	2100 East New York St
Aurora, IL 60507	Aurora, IL 605072067
Contact: City of Aurora 630/256-3650	Kane County
	Contact: Ian Wade 630/256-3200

### **Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	<b>Regulated Status</b>
1	Gasoline - Regular	20,000	Tank Not Installed	Federal
2	Gasoline - Regular	20,000	Tank Not Installed	Federal
3	Diesel Fuel	20,000	Tank Not Installed	Federal
4	Diesel Fuel	20,000	Tank Not Installed	Federal

# Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Spill Containment Device	Double Wall Spill Bucket	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Overfill Prevention Device	Overfill Alarm	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Tank	Fiberglass Double Wall XERXES	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Piping	Single Wall STP/Tanktop Sump	New
➡ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Shear Valves	New
Piping	Other Submersible Pump	New
Piping	Ball Valves	New

## Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Tank	Fiberglass Double Wall XERXES	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
🛏 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

# Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Tank	Fiberglass Double Wall XERXES	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
➡ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

## Tank 4 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Alarm	New
Tank	Fiberglass Double Wall XERXES	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Piping	Ball Valves	New
Piping	Other Submersible Pump	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Piping	Single Wall STP/Tanktop Sump	New
🛏 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Piping	Flex Connector Steel	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Piping	Shear Valves	New
Spill Containment Device	Double Wall Spill Bucket	New

# **Dispensers on the Permit**

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New

### **Dispenser 1/2 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
➡ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### **Dispenser 3/4 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
➡ Leak Detection - Piping	Sump Sensor with positive shutdown	New

#### **Dispenser 5/6 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
➡ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
➡ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### **General Requirements**

<u>USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.</u> There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

### **Summary of Work**

#### TANKS:

(2) 20,000 gallon 10' dia. double wall fiberglass tanks.

Concrete dead men hold downs, straps & turnbuckles.

Install (2) Monitoring wells in tank excavation.

OVERSPILL/OVERFILL PREVENTION:

(4) 5 gallon, below-grade level overspill containment manholes.

(4) OPW Overfill Valves.

SUMPS:

(4) 42" fiberglass water-tight piping sumps at tank tops.

(4) Under dispenser sumps at islands

PIPING:

2" Double wall UPP approved pipe system.

Ameron 2" single wall fiberglass vent piping system.

SUBMERSIBLE PUMPS:

(4) FE Petro submersible pumps with Electronic Line Leak Detector.

LEAK DETECTION:

(1) Veeder-Root TLS-450 monitor console.

(4) 10' Tank level probes.

(4) Tank interstitial sensors.

(4) Dispenser sump sensors.

(4) Tank sump sensors.

(4) Digital Pressurized line leak detectors.

(1) Overfill alarm with acknowledgement switch.

#### MANHOLES:

(4) 12" Observation well manhole.

- (4) 42" Composite manholes.
- (4) 18" Tank sensor manholes.

(4) 12" Manhole.

ISLAND EQUIPMENT:

(2) Fire extinguishers.

Self-Serve signage at islands.

DISPENSERS:

(4) Bennett brand dual product dispensers.

CANOPY: (1) Canopy

### Special Contingencies NOTE: Vents must meet section 175.440 of our rules

#### PERSON, FIRM OR COMPANY PERFORMING WORK:

Crowne Industries, Ltd. 651 S. Sutton Road #214 Streamwood, IL 60107	Contact Person: Robert Sumoski Phone: 630/201-4967 Email: bob@crownetank.com Contractor License # IL002345 Exp. 5/16/2026
--	--

Sincerely,

Janiel J. Starks

Daniel Starks