



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY	
Facility #:	1029129
Permit #:	00087-2025INS
Request Rec'd:	01/28/2025
Approval Date:	01/29/2025 DS
Permit Expires:	07/29/2025

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Thorntons, LLC 2600 James Thornton Way Louisville, KY 40245 Contact: Maggie Seaugh 502/572-1259	FACILITY - name and address where tanks are located: Thornton Oil #365 1810 N. Bloomington St. Streator, IL 61364 LaSalle County Contact: Karen Jordan 502/572-1176
--	--

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
7	Gasoline - Regular	20,000	Tank Not Installed	Federal
8	Gasoline - Premium	6,000	Tank Not Installed	Federal
9	Diesel Fuel	10,000	Tank Not Installed	Federal
10	E85	6,000	Tank Not Installed	Federal

Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall NOV Fiberglass Systems Red Thread IIA fiberglass piping	New
Piping	Flex Connector Steel	New
Piping	Other Fiberglass Riser	New
Piping	Other Steel Riser	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 8 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall NOV Fiberglass Systems Red Thread IIA fiberglass piping	New
Piping	Flex Connector Steel	New
Piping	Other Fiberglass Riser	New
Piping	Other Steel Riser	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 9 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall NOV Fiberglass Systems Red Thread IIA fiberglass piping	New
Piping	Flex Connector Steel	New
Piping	Other Fiberglass Riser	New
Piping	Other Steel Riser	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New


Tank 10 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall NOV Fiberglass Systems Red Thread IIA fiberglass piping	New
Piping	Flex Connector Steel	New
Piping	Other Fiberglass Riser	New
Piping	Other Steel Riser	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New


Dispensers on the Permit

Dispenser	Action
1/2	Replacing - 1/2
3/4	Replacing - 3/4
5/6	Replacing - 5/6
7/8	Replacing - 7/8
9/10	Replacing - 9/10
11/12	Replacing - 11/12
13	Removing
14	Removing


Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New


Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New


Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New


Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 13 Equipment

Equipment Type	Permit Equipment	Action
----------------	------------------	--------

Dispenser 14 Equipment

Equipment Type	Permit Equipment	Action
----------------	------------------	--------

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Installing new Xerxes DW tanks, 3 over 2 red thread fiberglass piping, FE Petro motors, DW spill buckets and vapory recovery buckets, new UDC's with positive shut down sump sensors, new STP sumps with sensors, Gilbarco 700 series dispensers, TLS 450 plus tank monitor and ATG probes, vent stack with alarm, OPW drop tubes.

Special Contingencies

NOTES: Vents must meet section 175.440 of our rules. Dispensers must maintain a full 10' to all buildings and property lines.

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Seneca Companies, Inc. 4140 East 14th Street PO Box 3360 Des Moines, IA 50313	Contact Person: Glen Davis Phone: 515/601-6635 Email: jfranklin@senecaco.com Contractor License # IL598 Exp. 2/23/2026

Sincerely,



Daniel Starks