



City of Chicago
Department of Public Health
333 South State Street, Room 200
Chicago, IL 60604
312/745-3162
www.sfm.illinois.gov
SFM.DPCS@illinois.gov
Extended

FOR OFFICE USE ONLY
Facility #: 2021476
Permit #: 00221-2024INS
Request Rec'd: 02/22/2024
Approval Date: 02/26/2024
Extension Date: 02/04/2025
Permit Expires: 08/27/2025

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE EXTENSION DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Rockbuild Enterprises, Inc. 3720 Albert Lane Long Grove, IL 60047 Lake County Contact: Mohammad Khan 312/685-7363	FACILITY - name and address where tanks are located: Rockbuild Enterprises, Inc. d/b/a Kedzie Auto Service 5301 S. Kedzie Chicago, IL 60632 Cook County Contact: Mohammad Khan 312/685-7363
---	--

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
6	Gasoline - Regular	12,000	Installed/Not in Use	Federal
7	Diesel Fuel	6,000	Installed/Not in Use	Federal
8	Gasoline - Premium	4,000	Installed/Not in Use	Federal

Tank 6 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Single Wall STP/Tanktop Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Single Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Single Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

Tank 8 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Single Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

Dispensers on the Permit

Dispenser	Action
Dispenser 1/2	New
Dispenser 3/4	New
Dispenser 5/6	New
Dispenser 7/8	New

Dispenser Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔌 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔌 Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

The site was permitted by a different contractor in 2022 and left the project after secondary piping and containmnet inspection. He re poured the concrete and never got the complinace testing and and all other OSFM Paper work. So we are taking over and OSFM inspector wants us to get the compliance testes finished and close the project from this point.

Special Contingencies

PERSON, FIRM OR COMPANY PERFORMING WORK:	
America Petropump Services LLC d/b/a Ampsco Services 4075 Fox Valley Center Dr., Unit 9 Aurora, IL 60504	Contact Person: Ravindra Penmatsa Phone: 312/286-6722 Email: ravi@ampsco.net Contractor License # IL002420 Exp. 5/22/2025

Sincerely,

sean.keane