



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 1027942
Permit #: 00448-2025UPG
Request Rec'd: 04/16/2025
Approval Date: 04/16/2025 DS
Permit Expires: 10/16/2025

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for
Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: GPM Midwest, LLC 8565 Magellan Pkwy, Ste. 400 Richmond, VA 23227 (None) County Contact: Rolfe Lann 804/730-1568	FACILITY - name and address where tanks are located: Fas Mart #5142 4106 Harrison Ave. Rockford, IL 61108 Winnebago County Contact: Jammie Miller 804/316-5227
---	---

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	12,000	Currently in use	Federal
2	Gasoline - Premium	10,000	Currently in use	Federal
3	Gasoline - Non Ethanol	4,000	Currently in use	Federal

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Ball Float Vent Valve

Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Ball Float Vent Valve

Summary of Work

REC 90 no drop tube exists, ball float fails testing. Install overfill valve, decommission ball float.
PUL straight drop tube exists, ball float fail testing. Install overfill valve, decommission ball float.
RUL straight drop tube exists, ball float passes testing. Install overfill valve.

Special Contingencies

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Stenstrom Petroleum Services Group 2422 Center Street Rockford, IL 61108	Contact Person: Robert Stenstrom Phone: 815/520-5292 Email: trevorh@rstenstrom.com Contractor License # IL1890 Exp. 4/12/2026

Sincerely,

Daniel J. Starks

Daniel Starks