



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**

1035 Stevenson Drive
Springfield, IL 62703
217/785-1020

www.sfm.illinois.gov
SFM.DPCS@illinois.gov

Revised

Replacement of 00644-2024INS

FOR OFFICE USE ONLY

Facility #: 2047753
Permit #: 01627-2024INS
Request Rec'd: 12/17/2024
Approval Date: 12/17/2024 DS
Revision Date: 04/21/2025 DS
Permit Expires: 06/17/2025

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Lenny's Gas N Wash 65th & Central, LLC 8200 W 185th St. Unit K Tinley Park, IL 60487 Contact: Leonard McEnery 708/444-0117	FACILITY - name and address where tanks are located: Lenny's Gas N Wash 65th & Central, LLC 5611 W 65th Street Bedford Park, IL 60638 Cook County Contact: Leonard McEnery 708/444-0117
---	--

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	20,000	Installed/Not in Use	Federal
2	Gasoline - Premium	6,000	Installed/Not in Use	Federal
3	E85	10,000	Installed/Not in Use	Federal
4	Diesel Fuel	6,000	Installed/Not in Use	Federal
5	Diesel Fuel	20,000	Installed/Not in Use	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors With Monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors With Monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors With Monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 4 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors With Monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors With Monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New
9/10	New
11/12	New
13/14	New
15/16	New
17/18	New
19/20	New
21/22	New
23/24	New
25/26	New
27/28	New
29M	New
29S/30M	New
30S/31M	New
31S/32M	New
32S	New

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 13/14 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 15/16 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 17/18 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 19/20 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 21/22 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 23/24 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 25/26 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 27/28 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 29M Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 29S/30M Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 30S/31M Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 31S/32M Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 32S Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Installing new station per the attached.

Customer shifted tanks away from property line. See new drawing. Everything else remains the same.

ALL SEWERS AND SEWER GASKETS WITHIN THE SET BACK AREA ARE PETROLEUM RESISTANT NITRIL GASKETS AND DUCTAL IRON PIPE.

Special Contingencies**Amendment Reason #1:**

Customer shifted tank location away from property line.

Amendment Reason #2:

Inspector wants us to ammend permit to reflect that sewer lines and joints are petroleum resistant within the set back areas.

Replacement Reason:

Permit expired befopre job was completed.

Amendment Reason #1:

Customer shifted tank location away from property line.

Amendment Reason #2:

Inspector wants us to ammend permit to reflect that sewer lines and joints are petroleum resistant within the set back areas.

Revision Reason:

Changed the leak detection for the tank as requested by contractor

Replacement Reason:

Permit expired befopre job was completed.

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Anderson Pump Service, Inc. 19659 South 97th Avenue Mokena, IL 60448	Contact Person: Ron Anderson Phone: 708/243-9081 Email: Steve@andersonpump.com Contractor License # IL002275 Exp. 5/21/2026

Sincerely,



Daniel Starks