

Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 217/785-1020 www.sfm.illinois.gov SFM.DPCS@illinois.gov Replacement of 01298-2024INS FOR OFFICE USE ONLY

Facility #: 1001152
Permit #: 00463-2025INS
Request Rec'd: 04/21/2025
Approval Date:04/21/2025 DS
Permit Expires: 10/21/2025

<u>Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum</u> and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: https://webapps.sfm.illinois.gov/USTPortal/NotificationForm.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS

- Corporation, partnership, or other business entity:

Four Rivers Sanitation Authority 3501 Kishwaukee Street Rockford, IL 61109 (None) County

Contact: Jim Reader 815/387-7587

FACILITY

name and address where tanks are located:
 Rock River Water Reclamation District

3333 Kishwaukee Street Rockford, IL 61109

Winnebago County

Contact: Terry Stoll 815/387-7588

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
16	Dyed Diesel	6,000	Installed/Not in Use	Federal
17	Gasoline - Regular	6,000	Installed/Not in Use	Federal
18	Diesel Fuel	12,000	Installed/Not in Use	Federal

Tank 16 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Piping	Flexible Double Wall A.P.T. Poly Tech P175SC	New
Piping	Single Wall STP/Tanktop Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 17 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Piping	Flexible Double Wall A.P.T. Poly Tech P175SC	New
Piping	Single Wall STP/Tanktop Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 18 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Fiberglass Single Wall Piping Ameron 4000 L single wall vent	New
Piping	Flexible Double Wall A.P.T. Poly Tech P175SC	New
Piping	Single Wall STP/Tanktop Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements

<u>USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.</u>
There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Installing new fuel system. 3 compartment Xerxes double wall fiberglass tank. All piping to be APT XP-175SC. All vent piping Ameron 4000L.

System monitored by Veeder Root TLS-450Plus

Special Contingencies

NOTE: Dispensers must be a full 10' from buildings and property lines

Replacement Reason:

Oaniel J. Starke

Permit expired before final inspection was completed. Please issue new permit for final inspection.

PERSON, FIRM OR COMPANY PERFORMING WORK:		
Stenstrom Petroleum Services Group 2422 Center Street Rockford, IL 61108	Contact Person: Robert Stenstrom Phone: 815/209-6640 Email: natem@rstenstrom.com Contractor License # IL1890 Exp. 4/12/2026	

Sincerely,

Daniel Starks