



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 1015647
Permit #: 00465-2025INS
Request Rec'd: 04/21/2025
Approval Date: 04/21/2025 DS
Permit Expires: 10/21/2025

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

| | |
|--|---|
| OWNER OF TANKS - Corporation, partnership, or other business entity: City of Rockford 500 South Independence Ave. Rockford, IL 61102 Winnebago County Contact: Mark Kalousek 779/348-7664 | FACILITY - name and address where tanks are located: City of Rockford - City Yards 500 South Independence Ave. Rockford, IL 61102 Winnebago County Contact: Mark Kalousek 815/980-1703 |
|--|---|

Tanks on the Permit

| Tank # | Product | Capacity | Tank Status | Regulated Status |
|--------|--------------------|----------|--------------------|------------------|
| 23 | Gasoline - Regular | 20,000 | Tank Not Installed | Federal |
| 24 | Diesel Fuel | 20,000 | Tank Not Installed | Federal |

Tank 23 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L single wall vent | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P150SC | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Fiberglass Double Wall XERXES | New |

Tank 24 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L single wall vent | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P150SC | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| 🔗 Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Fiberglass Double Wall XERXES | New |

Dispensers on the Permit

| Dispenser | Action |
|-----------|----------|
| 1/2 | Removing |
| 3/4 | Removing |
| 5/6 | New |
| 7/8 | New |
| 9/10 | New |
| 11/12 | New |

Dispenser 1/2 Equipment

| Equipment Type | Permit Equipment | Action |
|----------------|------------------|--------|
|----------------|------------------|--------|

Dispenser 3/4 Equipment

| Equipment Type | Permit Equipment | Action |
|----------------|------------------|--------|
|----------------|------------------|--------|

Dispenser 5/6 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| 🔗 Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 7/8 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| 🔗 Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 9/10 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| 🔗 Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 11/12 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| Leak Detection - Piping | Sump Sensor with positive shutdown | New |

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work


Installing 2 new 20K DW Xerxes tanks, 4 new Bravo UDC, new APT CP150SC piping. Entire system monitored by new Veeder Root TLS-450Plus.

Special Contingencies

NOTES: Vents must meet section 175.440 of rules. Dispensers must be at least 10' from all buildings and property lines.

| PERSON, FIRM OR COMPANY PERFORMING WORK: | |
|--|--|
| Stenstrom Petroleum Services Group 2422 Center Street Rockford, IL 61108 | Contact Person: Robert Stenstrom Phone: 815/209-6640 Email: natem@rstenstrom.com Contractor License # IL1890 Exp. 4/12/2026 |

Sincerely,



Daniel Starks