



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov

**FOR OFFICE USE ONLY**  
Facility #: 1045429  
Permit #: 00574-2025UPG  
Request Rec'd: 05/09/2025  
Approval Date: 05/12/2025 DS  
Permit Expires: 11/13/2025

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for  
Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: Love's Travel Stops & Country Stores, Inc. 10601 N. Penn P.O. Box 26210 Oklahoma City, OK 73120 Contact: Kyle Collins 405/834-0311	<b>FACILITY</b> - name and address where tanks are located: Love's Travel Stop #529 1001 W. Walnut Street Oglesby, IL 61348 LaSalle County Contact: Monica Snell 405/602-6640
---	---

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Premium	8,000	Currently in use	Federal
2	Gasoline - Regular	12,000	Currently in use	Federal
3	Gasoline - Regular	20,000	Currently in use	Federal

**Tank 1 Equipment**

Equipment Type	Permit Equipment	Action
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX - North	New

**Tank 2 Equipment**

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve
Piping	Blending Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX - North	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New

**Tank 3 Equipment**

Equipment Type	Permit Equipment	Action
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX - North	New


**Summary of Work**

We will break out concrete over Siphon UL, UL and Premium tanks and electrical trench to building. Install dual meter blending sump, dual meter assembly and sump sensor. Reroute UL siphon line into new dual meter sump. Run new line from dual meter blending sump to Premium STP sump. Remove siphon suction leg and re-install in Premium STP Sump. Install new sub pump in Siphon UL sump for E98. Install new drop tube in E98 tank. Run new conduits to building. Tank 1 and Tank 3 piping will be broke for the blending sump addition.

**Special Contingencies**

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Illinois Oil Marketing Equipment, Inc. 850 Brenkman Drive Pekin, IL 61554	Contact Person: Bryan Estes Phone: 309/202-0792 Email: amannino@iome.com Contractor License # IL1293 Exp. 2/4/2026

Sincerely,



---

Daniel Starks