



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 2047413
Permit #: 00576-2025UPG
Request Rec'd: 05/09/2025
Approval Date: 05/12/2025 DS
Permit Expires: 11/13/2025

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for
Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Love's Travel Stops & Country Stores, Inc. 10601 N. Penn P.O. Box 26210 Oklahoma City, OK 73120 Contact: Kyle Collins 405/834-0311	FACILITY - name and address where tanks are located: Love's Travel Stops #859 8909 N. Brisbin Rd Morris, IL 60450 Grundy County Contact: Kyle Collins 405/834-0311
---	---

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	20,000	Currently in use	Federal
2	Gasoline - Regular	12,000	Currently in use	Federal
3	Gasoline - Premium	8,000	Currently in use	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Sump Sensor with positive shutdown in Single Wall Transition Sump H Valve Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown - North in Single Wall STP/Tanktop Sump	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP - North	New

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve
Piping	Blending Sump - South	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Blending Sump - North	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP - North	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New

Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Piping	Flexible Double Wall Franklin Fueling Systems UPP - North	New

Summary of Work

We will break out concrete over Siphon UL, UL and Premium tanks and electrical trench to building. Install dual meter blending sump, dual meter assembly and sump sensor. Reroute UL siphon line into new dual meter sump. Run new line from dual meter blending sump to Premium STP sump. Remove siphon suction leg and re-install in Premium STP Sump. Install new sub pump in Siphon UL sump for E98. Install new drop tube in E98 tank. Run new conduits to building. Added tank 1 & tank 3, piping to be broken to add blending sump

Special Contingencies

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Illinois Oil Marketing Equipment, Inc. 850 Brenkman Drive Pekin, IL 61554	Contact Person: Bryan Estes Phone: 309/202-0792 Email: amannino@iome.com Contractor License # IL1293 Exp. 2/4/2026

Sincerely,



Daniel Starks