



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov
Amended

FOR OFFICE USE ONLY
Facility #: 2001089
Permit #: 00568-2025UPG
Request Rec'd: 05/09/2025
Approval Date: 05/12/2025 DS
Amended Date: 08/01/2025 SB
Permit Expires: 11/13/2025

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Love's Travel Stops & Country Stores, Inc. 10601 N. Penn P.O. Box 26210 Oklahoma City, OK 73120 Contact: Kyle Collins 405/834-0311	FACILITY - name and address where tanks are located: Love's Travel Stop #606 1533 E. 162nd Street South Holland, IL 60473 Cook County Contact: Gibson James 312/339-7400
---	---

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
7	E98	12,000	Currently in use	Federal

Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve
Piping	Blending Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX - North	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New

Summary of Work

We will break out concrete over Siphon UL, UL and Premium tanks and electrical trench to building. Install dual meter blending sump, dual meter assembly and sump sensor. Reroute UL siphon line into new dual meter sump. Run new line from dual meter blending sump to Premium STP sump. Remove siphon suction leg and re-install in Premium STP Sump. Install new sub pump in Siphon UL sump for E98. Install new drop tube in E98 tank. Run new conduits to building. add piping for tank 6 and tank 8

Special Contingencies

Amendment Reason #1:


Adding Tank 6 and Tank 8 which we will be breaking piping on to add the blending sump

Amendment Reason #2:

Adding piping Electronic line leak detector

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Illinois Oil Marketing Equipment, Inc. 850 Brenkman Drive Pekin, IL 61554	Contact Person: Bryan Estes Phone: 309/202-0792 Email: amannino@iome.com Contractor License # IL1293 Exp. 2/4/2026

Sincerely,



Daniel Starks