



**City of Chicago**  
**Department of Public Health**  
333 South State Street, Room 200  
Chicago, IL 60604  
312/745-3162  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov  
**Replacement of 00824-2023INS**

**FOR OFFICE USE ONLY**  
Facility #: 2017661  
Permit #: 01114-2025INS  
Request Rec'd: 08/25/2025  
Approval Date: 08/25/2025 SK  
Permit Expires: 02/25/2026

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: East-West Properties, LLC 8603 W. 142nd Street Orland Park, IL 60461 Cook County Contact: Muhammad Khan 773/490-3696	<b>FACILITY</b> - name and address where tanks are located: BP 119 S. Cicero Avenue Chicago, IL 60644 Cook County Contact: Muhammad Khan 773/490-3696
--	---

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
12	Gasoline - Regular	12,000	Installed/Not in Use	Federal
13	Gasoline - Premium	4,000	Installed/Not in Use	Federal
14	Diesel Fuel	4,000	Installed/Not in Use	Federal
15	E85	4,000	Installed/Not in Use	Federal

**Tank 12 Equipment**

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Extractor Fitting Valves	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Lannon	New

**Tank 13 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Extractor Fitting Valves	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Lannon	New

**Tank 14 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Extractor Fitting Valves	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Lannon	New

## Tank 15 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Extractor Fitting Valves	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Lannon	New

## Dispensers on the Permit

Dispenser	Action
Dispenser-1/2	Replacing - 1/2
Dispenser- 3/4	Replacing - 3/4
Dispenser-5/6	Replacing - 5/6
Dispenser-7/8	Replacing - 7/8
9/10	Removing

## Dispenser Dispenser-1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser Dispenser- 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser Dispenser-5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser Dispenser-7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
----------------	------------------	--------

### General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

### Summary of Work

We are installing new Tanks, Piping, UDCs, Tank top sumps and islands

### Special Contingencies

### Replacement Reason:

ORIGINAL PERMIT EXPIRED BEFORE ALL WORK WAS FINISHED

PERSON, FIRM OR COMPANY PERFORMING WORK:	
America Petropump Services LLC d/b/a Ampsco Services 4075 Fox Valley Center Dr., Unit 9 Aurora, IL 60504	Contact Person: Ravindra Penmatsa Phone: 312/286-6722 Email: ravi@ampsco.net Contractor License # IL002420 Exp. 5/22/2027

Sincerely,

Sean Keane