

Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 217/785-1020 www.sfm.illinois.gov SFM.DPCS@illinois.gov FOR OFFICE USE ONLY

Facility #: 5047946
Permit #: 01291-2025INS
Request Rec'd: 10/03/2025
Approval Date:10/03/2025 DS
Permit Expires: 04/03/2026

<u>Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances</u>

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: https://webapps.sfm.illinois.gov/USTPortal/NotificationForm.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS

- Corporation, partnership, or other business entity:
MIT ROCHESTER DEVELOPMENT LLC
1230 COMMUNITY DRIVE
Rochester, IL 62563

Contact: MIT ROCHESTER DEVELOPMENT LLC 573/644-

4800

FACILITY

- name and address where tanks are located:

SUPER STATION 1230 COMMUNITY DRIVE Rochester, IL 62563 Sangamon County

Contact: MIT PATEL 573/644-4800

Tanks on the Permit

| Tank # | Product | Capacity | Tank Status | Regulated Status |
|--------|------------------------|----------|--------------------|------------------|
| 1 | Gasoline - Regular | 10,000 | Tank Not Installed | Federal |
| 2 | B-11 | 10,000 | Tank Not Installed | Federal |
| 3 | Gasoline - Premium | 5,000 | Tank Not Installed | Federal |
| 4 | Gasoline - Non Ethanol | 5,000 | Tank Not Installed | Federal |

Tank 1 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Jacketed Steel Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Ball Valves | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Single Wall Piping Vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P175SC | New |
| Piping | Other Steel Riser | New |
| Piping | Other Submersible Pump | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| → Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Tank 2 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Jacketed Steel Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Ball Valves | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Single Wall Piping Vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P175SC | New |
| Piping | Other Steel Riser | New |
| Piping | Other Submersible Pump | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Tank 3 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Jacketed Steel Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Ball Valves | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Single Wall Piping Vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P175SC | New |
| Piping | Other Steel Riser | New |
| Piping | Other Submersible Pump | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Tank 4 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|---|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Jacketed Steel Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Ball Valves | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Single Wall Piping Vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech P175SC | New |
| Piping | Other Steel Riser | New |
| Piping | Other Submersible Pump | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Dispensers on the Permit

| Dispenser | Action |
|-----------|--------|
| 1/2 | New |
| 3/4 | New |
| 5/6 | New |
| 7/8 | New |
| 9/10 | New |
| 11/12 | New |
| 13 | New |

Dispenser 1/2 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 3/4 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 5/6 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 7/8 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 9/10 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 11/12 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 13 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

INSTALLING NEW TANKS ISLANDS CANOPY AND PIPING

Special Contingencies

NOTES: Dispensers must be 10' from all buildings and property lines. Vents must meet section 175.440 of our rules.

PERSON, FIRM OR COMPANY PERFORMING WORK:

W J Scott Company 3861 Tozer Road Springfield, IL 62707

Daniel J. Starke

Contact Person: Jim Scott Phone: 217/415-0345 Email: jimswjs@comcast.net

Contractor License # IL1949 Exp. 4/18/2026

Sincerely,

Daniel Starks