

City of Chicago Department of Public Health

333 South State Street, Room 200 Chicago, IL 60604 312/745-3162 www.sfm.illinois.gov SFM.DPCS@illinois.gov FOR OFFICE USE ONLY

Facility #: 2047783
Permit #: 01352-2025INS
Request Rec'd: 10/12/2025
Approval Date:10/14/2025 SK
Permit Expires: 04/14/2026

<u>Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum</u> and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: https://webapps.sfm.illinois.gov/USTPortal/NotificationForm.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS

- Corporation, partnership, or other business entity: University of Chicago Medical Center 5841 S. Maryland Avenue Chicago, IL 60637 Cook County

Contact: Heather Sims 815/514-7041

FACILITY

name and address where tanks are located:
 University of Chicago Cancer Center
 5644 S. Drexel Avenue
 Chicago, IL 60636
 Cook County

Contact: John Veronesi 773/834-4011

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Diesel Fuel	25,000	Tank Not Installed	Federal
2	Diesel Fuel	25,000	Tank Not Installed	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	American with Sensors/No Test Suction	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Leak Detection - Tank	Required Other Veeder Root TLS 450 Monitor only for sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Fiberglass Double Wall	New
Piping	Single Wall Transition Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device Double Wall Spill Bucket Remote Fill		New
Tank	Fiberglass Double Wall XERXES	

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	American with Sensors/No Test Suction	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Leak Detection - Tank	Required Other Veeder Root TLS 450 Monitor only for sensors	New
Overfill Prevention Device	fill Prevention Device Overfill Alarm	
Piping	Fiberglass Double Wall	New
Piping	Single Wall Transition Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device Double Wall Spill Bucket Remote Fill		New
nk Fiberglass Double Wall XERXES		New

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Install (2) new 25,000 gallon double wall tanks with tank sumps, transition sump, double wall overspills, overfill alarm, double wall product piping, and single wall vent piping.

Special Contingencies

PERSON, FIRM OR COMPANY PERFORMING WORK:				
Metro Environmental Contractors, Inc. dba Metro Tank &	Contact Person: Warren Cherner			
Pump Company	Phone: 847/465-4000			
1111 West Dundee Road	Email: warren@metrotank.com			
Wheeling, IL 600903936	Contractor License # IL102 Exp. 9/20/2027			

Sincerely,

Sean Keane