



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 2000258
Permit #: 01434-2025UPG
Request Rec'd: 10/28/2025
Approval Date: 10/28/2025 DS
Permit Expires: 04/28/2026

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Midlothian Amstar, Inc. 14506 S. Pulaski Rd. Midlothian, IL 60445 (None) County Contact: Imtiaz Memon 708/597-9414	FACILITY - name and address where tanks are located: Midlothian Amstar, Inc. 14506 S. Pulaski Rd. Midlothian, IL 60445 Cook County Contact: Imtiaz Memon 708/597-9414
--	--

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	10,000	Currently in use	Federal
2	Gasoline - Premium	10,000	Currently in use	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	Replacing - Leak Detect - Piping - Electronic Pressurized Line Leak Detection
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350j with CSLD
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve
Piping	Ball Valves	New
Piping	Fiberglass Double Wall Ameron	Replacing - Piping - Fiberglass Double Wall Ameron
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	Replacing - Leak Detect - Piping - Electronic Pressurized Line Leak Detection
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350j with CSLD
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve
Piping	Ball Valves	New
Piping	Fiberglass Double Wall Ameron	Replacing - Piping - Fiberglass Double Wall Ameron
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	Replacing - Spill Contain Device - Single Wall Spill Bucket

Dispensers on the Permit

Dispenser	Action
1/2	Sump / Sensors Changing
3/4	Sump / Sensors Changing

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New

Summary of Work

Tanks # 1 & 2 = Installing new : STP sumps with sensors, UDC sumps with sensors, submersibles, fill risers. Replacing : up to 6' of product line per tank to install STP Sumps, up to 6' of product line per Dispensers 1/2 & 3/4 to install UDC Sumps, overspill buckets, overfill drop tubes, and TLS 450 Plus.

Special Contingencies

NOTE: Only installing enough new piping to accomodate new STP sumps and UDCs

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Anderson Pump Service, Inc. 19659 South 97th Avenue Mokena, IL 60448	Contact Person: Ron Anderson Phone: 708/560-5590 Email: Keith@Andersonpump.com Contractor License # IL002275 Exp. 5/21/2026

Sincerely,



Daniel Starks

For Office Use Only**Tank 1 Equipment**

Equipment Type	Permit Equipment	Action
Piping	Not Installed STP/Tanktop Sump	Removing

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Piping	Not Installed STP/Tanktop Sump	Removing

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing