

Office of the Illinois State Fire Marshal **Division of Petroleum and Chemical Safety**

1035 Stevenson Drive Springfield, IL 62703 217/785-1020 www.sfm.illinois.gov SFM.DPCS@illinois.gov Revised

FOR OFFICE USE ONLY

Facility #: 2041759 Permit #: 00778-2025UPG Request Rec'd: 06/24/2025 Approval Date:06/24/2025 DS Revision Date: 11/04/2025 DS Permit Expires: 12/24/2025

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for **Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS

- Corporation, partnership, or other business entity:

Mac's Convenience Stores, LLC 1100 Situs Court, Suite 100 Raleigh, NC 27606

(None) County

Contact: Michele Alvarado 773/456-5280

FACILITY

- name and address where tanks are located:

Circle K #1387 901 Dixie Highway Beecher, IL 60401 Will County

Contact: Todd Nurmi 815/933-3365

Tanks on the Permit

| Tank # | Product | Capacity | Tank Status | Regulated Status |
|--------|--------------------|----------|------------------|------------------|
| 1 | Gasoline - Regular | 15,000 | Currently in use | Federal |
| 2 | Diesel Fuel | 10,000 | Currently in use | Federal |
| 3 | Gasoline - Regular | 8,000 | Currently in use | Federal |
| 4 | Gasoline - Premium | 7,000 | Currently in use | Federal |

Tank 1 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|--|--|
| Corrosion Protection - Piping | Flexible Non-Corrosive | Replacing - Corrosion Prot - Piping - Flexible Non- Corrosive - Existing product piping being removed |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | Replacing - Leak Detect - Piping - Electronic Pressurized Line Leak Detection |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Red Jacket Pro Max with CSLD |
| Overfill Prevention Device | Overfill Drop Tube Valve | Replacing - Overfill Prev Device - Overfill Drop Tube Valve |
| Piping | Flexible Double Wall NUPI Smartflex | Replacing - Piping - Flexible Double Wall A.P.T. Poly Tech P175SC |
| Piping | Single Wall STP/Tanktop Sump | Replacing - Piping - Single Wall STP/Tanktop Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | Replacing - Spill Contain Device - Double Wall Spill Bucket |

Tank 2 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|--|--|
| Corrosion Protection - Piping | Flexible Non-Corrosive | Replacing - Corrosion Prot - Piping - Flexible Non- Corrosive - Existing product piping being removed |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | Replacing - Leak Detect - Piping - Electronic Pressurized Line Leak Detection |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Red Jacket Pro Max with CSLD |
| Overfill Prevention Device | Overfill Drop Tube Valve | Replacing - Overfill Prev Device - Overfill Drop Tube Valve |
| Piping | Flexible Double Wall NUPI Smartflex | Replacing - Piping - Flexible Double Wall A.P.T. Poly Tech P175SC |
| Piping | Single Wall STP/Tanktop Sump | Replacing - Piping - Single Wall STP/Tanktop Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | Replacing - Spill Contain Device - Double Wall Spill Bucket |

Tank 3 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|--|--|
| Corrosion Protection - Piping | Flexible Non-Corrosive | Replacing - Corrosion Prot - Piping - Flexible Non- Corrosive - Existing product piping being removed |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | Replacing - Leak Detect - Piping - Electronic Pressurized Line Leak Detection |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Red Jacket Pro Max with CSLD |
| Overfill Prevention Device | Overfill Drop Tube Valve | Replacing - Overfill Prev Device - Overfill Drop Tube Valve |
| Piping | Flexible Double Wall NUPI Smartflex | Replacing - Piping - Flexible Double Wall A.P.T. Poly Tech P175SC |
| Piping | Single Wall STP/Tanktop Sump | Replacing - Piping - Single Wall STP/Tanktop Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | Replacing - Spill Contain Device - Single Wall Spill Bucket |

Tank 4 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|--|--|
| Corrosion Protection - Piping | Flexible Non-Corrosive | Replacing - Corrosion Prot - Piping - Flexible Non- Corrosive - Existing product piping being removed |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | Replacing - Leak Detect - Piping - Electronic Pressurized Line Leak Detection |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Red Jacket Pro Max with CSLD |
| Overfill Prevention Device | Overfill Drop Tube Valve | Replacing - Overfill Prev Device - Overfill Drop Tube Valve |
| Piping | Flexible Double Wall NUPI Smartflex | Replacing - Piping - Flexible Double Wall A.P.T. Poly Tech P175SC |
| Piping | Single Wall STP/Tanktop Sump | Replacing - Piping - Single Wall STP/Tanktop Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | Replacing - Spill Contain Device - Single Wall Spill Bucket |

Dispensers on the Permit

| Dispenser | Action |
|-----------|------------------|
| 1/2 | Replacing - 1/2 |
| 3/4 | Replacing - 3/4 |
| 5/6 | Replacing - 5/6 |
| 7/8 | Replacing - 7/8 |
| 9/10 | Replacing - 9/10 |

Dispenser 1/2 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--|
| Dispenser | Single Wall UDC Sump | Replacing - Dispenser - Single Wall UDC Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 3/4 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--|
| Dispenser | Single Wall UDC Sump | Replacing - Dispenser - Single Wall UDC Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 5/6 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--|
| Dispenser | Single Wall UDC Sump | Replacing - Dispenser - Single Wall UDC Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 7/8 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--|
| Dispenser | Single Wall UDC Sump | Replacing - Dispenser - Single Wall UDC Sump |
| ► Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 9/10 Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--|
| Dispenser | Single Wall UDC Sump | Replacing - Dispenser - Single Wall UDC Sump |
| → Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Summary of Work

All Tank and Island locations to remain the same. Replacing product lines, overspill buckets, overfill drop tubes, Submersibles, STP sumps/sensors, UDC sumps/sensors, TLS 450 plus. (2) New E-Stops as per attached drawing.

Special Contingencies

NOTE: Dispensers must be a full 10' from all buildings and property lines.

Revision Reason:

Added spill buckets on tanks 3 & 4

| PERSON, FIRM OR COMPANY PERFORMING WORK: | | |
|--|---|--|
| Anderson Pump Service, Inc. 19659 South 97th Avenue Mokena, IL 60448 | Contact Person: Ron Anderson Phone: 708/560-5590 Email: Keith@Andersonpump.com Contractor License # IL002275 Exp. 5/21/2026 | |

Daniel Starks

For Office Use Only

Tank 1 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|--|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

Tank 2 Equipment

| Action | Permit Equipment | Equipment Type |
|----------|--|-------------------------|
| Removing | Piping Sump Sensors Not Regulated Not Required | Leak Detection - Piping |
| | in Single Wall STP/Tanktop Sump | Leak Detection - Piping |

Tank 3 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|--|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

Tank 4 Equipment

| Equipment Type | Permit Equipment | Action |
|--------------------------|--|----------|
| Treak Defection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

Dispenser 1/2 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|--|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

Dispenser 3/4 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|--|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required | Removing |
| | in Single Wall UDC Sump | Kemoving |

Dispenser 5/6 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|--|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

Dispenser 7/8 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|--|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

Dispenser 9/10 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------|--|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |