

# Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 217/785-1020 www.sfm.illinois.gov SFM.DPCS@illinois.gov Replacement of 00091-2025INS FOR OFFICE USE ONLY

Facility #: 2047852
Permit #: 01509-2025INS
Request Rec'd: 11/06/2025
Approval Date:11/12/2025 DS
Permit Expires: 05/12/2026

# <u>Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum</u> and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: https://webapps.sfm.illinois.gov/USTPortal/NotificationForm.

## THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

#### **OWNER OF TANKS**

- Corporation, partnership, or other business entity:

123 Blue Island Property LLC 12308 S Western Ave. Blue Island, IL 60406

Contact: 123 Blue Island Property LLC 630/290-3166

#### **FACILITY**

- name and address where tanks are located:

Blue Island One Stop 76 12300 S WESTERN AVENUE Blue Island, IL 60406 Cook County

Contact: AHMED MOHSIN 630/290-3166

#### **Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Premium	8,000	Installed/Not in Use	Federal
2	E85	7,000	Installed/Not in Use	Federal
3	Gasoline - Regular	20,000	Installed/Not in Use	Federal

### **Tank 1 Equipment**

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Ball Valves	New
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	New
Piping	Flexible Single Wall Piping	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket Remote Fill	New
Tank	Composite Double Wall Lannon	New

# **Tank 2 Equipment**

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Ball Valves	New
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	New
Piping	Flexible Single Wall Piping	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket Remote Fill	New
Tank	Composite Double Wall Lannon	New

# Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Ball Valves	New
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	New
Piping	Flexible Single Wall Piping	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket Remote Fill	New
Tank	Composite Double Wall Lannon	New

# Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New
9/10	New

# Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

## **Dispenser 3/4 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

## **Dispenser 5/6 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

# Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
► Leak Detection - Piping	Sump Sensor with positive shutdown	New

## **General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

## **Summary of Work**

Permit application is for remote fills and to show location of remote fills. It is an amendment to the original permit #00091-2025INS

We are not installing 3 additional tanks.

### **Special Contingencies**

NOTES: Remote fills over 20 feet in length shall have interstitial monitoring and an audible and visible overfill alarm. Remote fills shall be sloped back to the tank. Vents must meet section 175.440 of our rules. Dispensers must be at least 10' from all buildings and property lines.

## **Replacement Reason:**

Oaniel J. Starks

Replacing permit 00091-2025INS because permit required another amendment due to equipment changes

PERSON, FIRM OR COMPANY PERFORMING WORK:		
B & K Equipment Company 2939 175th Street Lansing, IL 60438	Contact Person: DJ White Phone: 708/474-3344 Email: jim.veverka@bkequip.com Contractor License # IL1207 Exp. 2/14/2026	

Sincerely,

Daniel Starks