



**Office of the Illinois State Fire Marshal**  
**Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov

**FOR OFFICE USE ONLY**  
Facility #: 2047966  
Permit #: 01577-2025INS  
Request Rec'd: 11/13/2025  
Approval Date: 11/24/2025 DS  
Permit Expires: 05/27/2026

### **Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity:	<b>FACILITY</b> - name and address where tanks are located: Ricky Rockets 1250 Rock Run Crossings Drive Joliet, IL 60431 Will County Contact: Chase Heidner 630/894-0099
--	--

#### **Tanks on the Permit**

<b>Tank #</b>	<b>Product</b>	<b>Capacity</b>	<b>Tank Status</b>	<b>Regulated Status</b>
1	Gasoline - Regular	20,000	Tank Not Installed	Federal
2	E85	6,000	Tank Not Installed	Federal
3	Diesel Fuel	10,000	Tank Not Installed	Federal
4	Gasoline - Premium	6,000	Tank Not Installed	Federal

## Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veede Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Extractor Fitting Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Fiberglass Single Wall Piping Ameron Dualoy 3000/L	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veede Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Extractor Fitting Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Fiberglass Single Wall Piping Ameron Dualoy 3000/L	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

### Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veede Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Extractor Fitting Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Fiberglass Single Wall Piping Ameron Dualoy 3000/L	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

### Tank 4 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veede Root TLS 450 Plus	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Extractor Fitting Valves	New
Piping	Fiberglass Double Wall Ameron Dualoy 3000/LCX	New
Piping	Fiberglass Single Wall Piping Ameron Dualoy 3000/L	New
Piping	Flex Connector Steel	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New
9/10	New
11/12	New
13/14	New
15/16	New
17/18	New
19/20	New

### Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 13/14 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 15/16 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 17/18 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 19/20 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**

We are building a new Ricky Rockets, installing new tanks (Regular, Premium, E85, Diesel), and associated fiberglass piping.

**Special Contingencies**

**NOTES: Vents must meet section 175.440 of our rules. Dispensers must be 10' from all buildings and property lines.**

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Anderson Pump Service, Inc. 19659 South 97th Avenue Mokena, IL 60448	Contact Person: Ron Anderson Phone: 630/484-7374 Email: KeenanA@Andersonpump.com Contractor License # IL002275 Exp. 5/21/2026

Sincerely,

Daniel G. Starks

Daniel Starks