



**Office of the Illinois State Fire Marshal**  
**Division of Petroleum and Chemical Safety**  
 1035 Stevenson Drive  
 Springfield, IL 62703  
 217/785-1020  
 www.sfm.illinois.gov  
 SFM.DPCS@illinois.gov  
**Revised**

<b>FOR OFFICE USE ONLY</b>	
Facility #:	2012961
Permit #:	00970-2025INS
Request Rec'd:	07/24/2025
Approval Date:	07/28/2025 SB
Revision Date:	12/01/2025 DS
Permit Expires:	01/28/2026

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: Graham Enterprise, Inc. 750 Bunker Court Vernon Hills, IL 60061 Lake County Contact: Raymond Kirchner 847/837-0777	<b>FACILITY</b> - name and address where tanks are located: Skokie Quik Shop 5343 West Touhy Avenue Skokie, IL 60077 Cook County Contact: Paul Solis 847/254-7605
--	---

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
6	Gasoline - Premium	6,000	Installed/Not in Use	Federal
7	Gasoline - Regular	10,000	Installed/Not in Use	Federal
8	Gasoline - Regular	6,000	Installed/Not in Use	Federal

**Tank 6 Equipment**

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Modern Welding Glasteel II	New

## Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Modern Welding Glasteel II	New

## Tank 8 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Jacketed Steel Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350 with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Other Submersible Pump	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Modern Welding Glasteel II	New

## Dispensers on the Permit

Dispenser	Action
1/2	Replacing - 1/2
3/4	Replacing - 3/4
5/6	Replacing - 5/6
7/8	Replacing - 7/8

## Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 5/6 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 7/8 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	Replacing - Dispenser - Single Wall UDC Sump
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**

Installing (1) 22,000 gallon Modern Welding GSII 3-compartment tank with 6,000 gallon PUL / 10,000 gallon RUL / 6,000 gallon E15 compartments / tanks. Installing new SWFRP STP Sumps, new SW Nupi UDC's, new Nupi DW Smartflex product piping to islands, new Nupi SW Smartflex vent piping, new Veeder Root ATG probes, new Veeder Root PLLD's, New Veeder Root 323 Liquid Sensors at all Sumps & UDC's, new Veeder Root Interstitial Sensor, new Franklin Defender DW Spill Buckets (Fills), new Franklin Defender SW Spill Buckets (Stage I Vapor), new Franklin Defender Overfill Valves, new OPW Dbl Poppet Impact Valves and new FE Petro 1.5HP STP's. The existing Veeder Root TLS 350 is to remain.

**Special Contingencies****Revision Reason:**

Changed product in tank 8

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Performance Tank, Inc. 730 Creel Drive Wood Dale, IL 60191	Contact Person: Tim Berg Phone: 847/612-6551 Email: tberg@perftank.com Contractor License # IL881 Exp. 12/8/2026

Sincerely,



Shelly Bradley

**For Office Use Only****Dispenser 1/2 Equipment**

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump	Removing

**Dispenser 3/4 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Leak Detection - Piping	Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump	Removing

**Dispenser 5/6 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Leak Detection - Piping	Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump	Removing

**Dispenser 7/8 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Leak Detection - Piping	Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump	Removing