



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov
Amended

FOR OFFICE USE ONLY
Facility #: 7042092
Permit #: 01620-2025UPG
Request Rec'd: 12/04/2025
Approval Date: 12/04/2025 DS
Amended Date: 12/16/2025 DS
Permit Expires: 06/04/2026

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Love's Travel Stops & Country Stores, Inc. 10601 N. Penn P.O. Box 26210 Oklahoma City, OK 73120 Contact: Kyle Collins 405/834-0311	FACILITY - name and address where tanks are located: Love's Travel Stop #318 202 North Ave. Ina, IL 62846 Jefferson County Contact: Lance Canteloupe 405/302-6640
---	--

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
5	Gasoline - Premium	12,000	Currently in use	Federal

Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Sump Sensor with positive shutdown in Single Wall STP/Tanktop Sump	Replacing - Leak Detect - Piping - Sump Sensor
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	Replacing - Leak Detect - Tank - Non-Discriminating Interstitial Monitoring Sensors With Monitor
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve
Spill Containment Device	Double Wall Spill Bucket	New

Summary of Work

Sawcut and break concrete over Siphon Unleaded, Unleaded, and Premium tanks
Remove concrete and vac gravel to expose piping
Install dual meter sump, dual meter assembly, and sump sensor
Reroute Unleaded siphon line in to new dual meter sump
Run new line from dual meter sump to Premium STP sump
Remove siphon suction leg and re-install in Premium STP sump
Install new sub pump in Siphon Unleaded sump for E98
Test all piping and water test sumps
Once inspections are passed, backfill trench and tank area
Set manholes and prep for concrete.
Pour concrete over tanks
Install customer supplied TMS panel next to TLS per plans
Transfer bio controls to the TMS panel
Pull wire and make connections
Install new drop tube in E98 tank
Startup and test system
Adding a remote fill for Premium Tank 5

Special Contingencies

NOTE: Remove fill must meet section 175.445 of our rules

Amendment Reason:

We are adding a remote fill for Premium Tank 5

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Illinois Oil Marketing Equipment, Inc. 850 Brenkman Drive Pekin, IL 61554	Contact Person: Bryan Estes Phone: 309/678-8061 Email: pcarrabbia@iome.com Contractor License # IL1293 Exp. 2/4/2026

Sincerely,



Daniel Starks