



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov
Revised/Amended

| FOR OFFICE USE ONLY | |
|---------------------|---------------|
| Facility #: | 1033835 |
| Permit #: | 01020-2025INS |
| Request Rec'd: | 08/05/2025 |
| Approval Date: | 08/06/2025 DS |
| Amended Date: | 01/21/2026 DS |
| Revision Date: | 10/20/2025 DS |
| Permit Expires: | 02/06/2026 |

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

| | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>OWNER OF TANKS - Corporation, partnership, or other business entity: M&B Truck Stop Real Estate, Inc. 900 Petro Road Rochelle, IL 61068 (None) County Contact: Mike Boparai 916/396-1665</p> | <p>FACILITY - name and address where tanks are located: Petro Center Rochelle 900 Petro Drive Rochelle, IL 61068 Ogle County 25-17-300-008 Contact: Jill Sanders 815/562-8475</p> |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Tanks on the Permit

| Tank # | Product | Capacity | Tank Status | Regulated Status |
|--------|-------------|----------|----------------------|------------------|
| 11 | Diesel Fuel | 20,000 | Installed/Not in Use | Federal |
| 12 | Diesel Fuel | 20,000 | Installed/Not in Use | Federal |
| 13 | Diesel Fuel | 10,000 | Installed/Not in Use | Federal |
| 14 | B-99 | 10,000 | Installed/Not in Use | Federal |

Tank 11 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|-----------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Composite Non-Corrosive | New |
| Leak Detection - Piping | Mechanical Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Double Wall Ameron Dualoy 3000/LCX | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L single wall vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Tank 12 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|-----------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Composite Non-Corrosive | New |
| Leak Detection - Piping | Mechanical Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Double Wall Ameron Dualoy 3000/LCX | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L single wall vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Tank 13 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|-----------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Composite Non-Corrosive | New |
| Leak Detection - Piping | Mechanical Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Double Wall Ameron Dualoy 3000/LCX | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L single wall vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Tank 14 Equipment

| Equipment Type | Permit Equipment | Action |
|-------------------------------|-----------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Composite Non-Corrosive | New |
| Leak Detection - Piping | Mechanical Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Veeder Root TLS 450 Plus | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors With Monitor | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Extractor Fitting Valves | New |
| Piping | Fiberglass Double Wall Ameron Dualoy 3000/LCX | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L single wall vent | New |
| Piping | Flex Connector Steel | New |
| Piping | Shear Valves | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Composite Double Wall Modern Welding Glasteel II | New |

Dispensers on the Permit

| Dispenser | Action |
|-------------------|--------|
| 1 Master | New |
| 2 Master/ 1 Slave | New |
| 3 Master/ 2 Slave | New |
| 4 Master/ 3 Slave | New |
| 5 Master/ 4 Slave | New |
| 6 Master/ 5 Slave | New |
| 7 Master/ 6 Slave | New |
| 8 Master/ 7 Slave | New |
| 9 Master/ 8 Slave | New |
| 9/Slave | New |

Dispenser 1 Master Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 2 Master/ 1 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 3 Master/ 2 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 4 Master/ 3 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 5 Master/ 4 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 6 Master/ 5 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 7 Master/ 6 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 8 Master/ 7 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 9 Master/ 8 Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

Dispenser 9/Slave Equipment

| Equipment Type | Permit Equipment | Action |
|---------------------------|------------------------------------|--------|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.

There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

We are installing 3 20K DSL tanks along with pumps, piping and all required UST equipment.
We are also installing 8K GalsSteel tank for DEF

Special Contingencies

NOTES: Dispensers must be 10' from all buildings and property lines. Vents must meet section 175.440 of our rules.

Amendment Reason #1:

THE MATERIAL WAS SUPPLIED BY THE CUSTOMER AND MADE A MISTAKE IN PIPING TYPE

Amendment Reason #2:

The leak detectors are mechanical not digital . Customer supplied the parts

Revision Reason:

Changed tank sizes for tanks 13 and 14 to 10k apiece rather than 12k and 8k as originally permitted

| PERSON, FIRM OR COMPANY PERFORMING WORK: | |
|----------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|
| America Petropump Services LLC d/b/a Ampsco Services 4075 Fox Valley Center Dr., Unit 9 Aurora, IL 60504 | Contact Person: Ravindra Penmatsa Phone: 312/286-6722 Email: ravi@ampsco.net Contractor License # IL002420 Exp. 5/22/2027 |

Sincerely,



Daniel Starks