



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**

1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov

**FOR OFFICE USE ONLY**  
Facility #: 5023889  
Permit #: 00256-2026INS  
Request Rec'd: 02/26/2026  
Approval Date: 03/09/2026 DS  
Permit Expires: 09/09/2026

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p><b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: Chatham IL LLC 3772 Oakwood Cir Taylorville, IL 62568 (None) County Contact: Shamsheer Sargodhia 217/415-9226</p>	<p><b>FACILITY</b> - name and address where tanks are located: Highway Travel Plaza 100 N. Henrietta Divernon, IL 62530 Sangamon County 35-16.0-400-042 Contact: Andrew Yonke 217/415-9226</p>
--	--

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
4	Diesel Fuel	20,000	Tank Not Installed	Federal
5	Gasoline - Mid-grade	6,108	Tank Not Installed	Federal
6	Gasoline - Premium	6,108	Tank Not Installed	Federal
7	Gasoline - Regular	20,000	Tank Not Installed	Federal

#### Tank 4 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Franklin Fueling Systems EVO 600 with SCALD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall A.P.T. Poly Tech S175SC	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

#### Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Franklin Fueling Systems EVO 600 with SCALD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall A.P.T. Poly Tech S175SC	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Tank 6 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Franklin Fueling Systems EVO 600 with SCALD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall A.P.T. Poly Tech S175SC	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Franklin Fueling Systems EVO 600 with SCALD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall A.P.T. Poly Tech S175SC	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New
9/10	New
11 master	New
12 master	New

### Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 11 master Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### Dispenser 12 master Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

### General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

### Summary of Work

We propose to excavate for 3 new 20k Containment solutions double wall fiberglass tanks. slope walls as per requirements, grade bottom of hole, set deadmen anchors, bed bottom of hole with gravel, set tanks and tied down to anchors, backfill tank hole to top of tanks, install tank hardware, set dispenser sumps, run new d.w. apt flex pipe to all sumps, call for inspection, backfill to sub grade, install canopies, pour pavement, pull wire, set equipment, start up and place in service. Call for final inspection.

**Special Contingencies**


**NOTES: Vents must meet section 175.440 of our rules. Dispensers must be at least 10' from all buildings and property lines.**

**PERSON, FIRM OR COMPANY PERFORMING WORK:**

All Line Equipment, Inc.  
5519 Skyline Drive, PO Box 5257  
Quincy, IL 62305

Contact Person: Steve Disselhorst  
Phone: 217/224-9725  
Email: steve@all-lineequipment.com  
Contractor License # IL002319 Exp. 12/23/2027

Sincerely,

  
\_\_\_\_\_

Daniel Starks