



**City of Chicago**  
**Department of Public Health**  
 333 South State Street, Room 200  
 Chicago, IL 60604  
 312/745-3162  
[www.sfm.illinois.gov](http://www.sfm.illinois.gov)  
[SFM.DPCS@illinois.gov](mailto:SFM.DPCS@illinois.gov)  
**Replacement of 01205-2025INS**

<b>FOR OFFICE USE ONLY</b>	
Facility #:	2023067
Permit #:	00502-2026INS
Request Rec'd:	04/13/2026
Approval Date:	05/04/2026 SK
Permit Expires:	11/04/2026

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p><b>OWNER OF TANKS</b>                  - Corporation, partnership, or other business entity:                  Norko, LLC                  4400 W. North Avenue                  Chicago, IL 60639                  Cook County                  Contact: Tito Kandarappallil 847/323-3109</p>	<p><b>FACILITY</b>                  - name and address where tanks are located:                  Amoco 5025                  4400 West North Avenue                  Chicago, IL 60639                  Cook County                  13-34-319-025-0000                  Contact: Tito Kandarappallil 847/323-3109</p>
--	--

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
4	Gasoline - Regular	14,000	Installed/Not in Use	Federal
5	Gasoline - Premium	6,000	Installed/Not in Use	Federal

**Tank 4 Equipment**

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Mechanical Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Mechanical Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 350	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Containment Solutions	New

## Dispensers on the Permit

Dispenser	Action
1/2	Sump / Sensors Changing
3/4	Sump / Sensors Changing
5/6	Sump / Sensors Changing

## Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

## Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

## General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

## Summary of Work

INSTALLING NEW 20K SPLIT 14/6. 3 ISLANDS WITH EXISTING GAS DISPENSERS.

## Special Contingencies

### Replacement Reason:

GENERAL CONTACTOR ISSUES. PROJECT WAS DELAYED.

**PERSON, FIRM OR COMPANY PERFORMING WORK:**

Cardinal Compliance LLC  
415 W. Golf Rd. Unit 28M-N  
Arlington Heights, IL 60005

Contact Person: Chris Derro  
Phone: 708/717-2676  
Email: cderro@cardinalcompliance.net  
Contractor License # IL002418 Exp. 3/21/2027

Sincerely,

Sean Keane

**For Office Use Only**

**Dispenser 1/2 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Dispenser	Not Installed UDC Sump	Removing

**Dispenser 3/4 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Dispenser	Not Installed UDC Sump	Removing

**Dispenser 5/6 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Dispenser	Not Installed UDC Sump	Removing