



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**

1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov

**Revised**

**Replacement of 00541-2025INS**

FOR OFFICE USE ONLY	
Facility #:	2016444
Permit #:	00117-2026INS
Request Rec'd:	01/29/2026
Approval Date:	01/29/2026 DS
Revision Date:	05/05/2026 DS
Permit Expires:	07/29/2026

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p><b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity: 786 Business, LLC 14112 Pulaski Road Crestwood, IL 69418 Cook County Contact: Mazhar Bhattie 708/699-9237</p>	<p><b>FACILITY</b> - name and address where tanks are located: 76 McHenry 3702 W. Elm McHenry, IL 60050 McHenry County 09-26-376-021 Contact: Mazhar Bhatti 708/699-9237</p>
--	--

**Tanks on the Permit**

Tank #	Product	Capacity	Tank Status	Regulated Status
7	Gasoline - Regular	10,000	Installed/Not in Use	Federal
8	Gasoline - Premium	4,000	Installed/Not in Use	Federal
9	Diesel Fuel	4,000	Installed/Not in Use	Federal

**Tank 7 Equipment**

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Mechanical Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Flexible Single Wall Piping	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Modern Welding Glasteel II	New

### Tank 8 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Mechanical Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Flexible Single Wall Piping	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Modern Welding Glasteel II	New

### Tank 9 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Composite Non-Corrosive	New
Leak Detection - Piping	Mechanical Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Flexible Double Wall NUPI Smartflex	New
Piping	Flexible Single Wall Piping	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Composite Double Wall Modern Welding Glasteel II	New

### Dispensers on the Permit

Dispenser	Action
1/2	Sump / Sensors Changing
3/4	Sump / Sensors Changing
5/6	Sump / Sensors Changing
7/8	Sump / Sensors Changing

### Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 3/4 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 5/6 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**Dispenser 7/8 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**

INSTALLING 1-18K COMPARTMENT 10/4/4 SPLIT 4 ISLANDS

**Special Contingencies**

**NOTES: All dispensers must be at least 10' from buildings and property lines. Vents must meet section 175.440 of our rules**

**Replacement Reason:**

CUSTOMER WAS WORKING WITH VILLAGE TO OBTAIN OCCUPANCY.

**Revision Reason:**

Permit needed to show the overfill alarm, so I revised it to show it.

**Replacement Reason:**

CUSTOMER WAS WORKING WITH VILLAGE TO OBTAIN OCCUPANCY.

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Cardinal Compliance LLC 415 W. Golf Rd. Unit 28M-N Arlington Heights, IL 60005	Contact Person: Chris Derro Phone: 708/717-2676 Email: cderro@cardinalcompliance.net Contractor License # IL002418 Exp. 3/21/2027

Sincerely,



Daniel Starks

**For Office Use Only****Dispenser 1/2 Equipment**

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

**Dispenser 3/4 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Dispenser	Not Installed UDC Sump	Removing

**Dispenser 5/6 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Dispenser	Not Installed UDC Sump	Removing

**Dispenser 7/8 Equipment**

<b>Equipment Type</b>	<b>Permit Equipment</b>	<b>Action</b>
Dispenser	Not Installed UDC Sump	Removing