



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 6006789
Permit #: 00611-2026UPG
Request Rec'd: 06/01/2026
Approval Date: 06/02/2026 DS
Permit Expires: 12/02/2026

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for
Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: N & B Fuel Mart, Inc. 10229 State Route 3 Red Bud, IL 62278 Randolph County Contact: Rhonda Nobbe 618/282-2888	FACILITY - name and address where tanks are located: N & B Fuel Mart, Inc. 10229 State Route 3 Red Bud, IL 62278 Randolph County 13-025-011-00 Contact: Todd Birkner 618/282-2888
--	---

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
6	Diesel Fuel	10,000	Currently in use	Federal
7	Gasoline - Regular	12,000	Currently in use	Federal

Dispensers on the Permit

Dispenser	Action
1/3	Sump / Sensors Changing
2/4	Sump / Sensors Changing
5/7	Sump / Sensors Changing
6/8	Sump / Sensors Changing

Dispenser 1/3 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New

Dispenser 2/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New

Dispenser 5/7 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New

Dispenser 6/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New

Summary of Work

Remove dispensers.
Blow product lines out back to tanks with nitrogen.
Saw cut bust and remove concrete from 4 dispenser islands under gas canopy.
Excavate down to product lines and and pump boxes. Dig out enough a sump can be installed.
Cut product lines back 1'-2' to allow sump to be set in place.
Set dispenser sumps in place and secure.
Run product lines through entry boots into sumps.
Perform air test on product lines, once passed glue in entry boots.
Perform hydrostatic test on sumps.
Perform air and sump test with OSFM.
Backfill product lines and sumps.
Pour back concrete.
Set dispensers on sumps, pipe and wire up.
Purge and calibrate.
Perform precision line test on product lines.
Perform final inspection with OSFM.

Special Contingencies

NOTE: Installing new UDC

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Mid-South Steel Products, Inc. 2071 Corporate Circle Drive PO Box 277 Cape Girardeau, MO 63703	Contact Person: Billy Thorne Phone: 573/335-5529 Email: billy@midsouthsteel.com Contractor License # IL1194 Exp. 8/17/2026

Sincerely,



Daniel Starks

For Office Use Only

Dispenser 1/3 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 2/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 5/7 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 6/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing