



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov

|                            |               |
|----------------------------|---------------|
| <b>FOR OFFICE USE ONLY</b> |               |
| Facility #:                | 2048022       |
| Permit #:                  | 00641-2026INS |
| Request Rec'd:             | 06/03/2026    |
| Approval Date:             | 06/08/2026 DS |
| Permit Expires:            | 12/08/2026    |

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

|                                                                                                                                                                                           |                                                                                                                                                                               |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>OWNER OF TANKS</b><br>- Corporation, partnership, or other business entity:<br>QuikTrip Corporation<br>4705 S. 129th East Avenue<br>Tulsa, OK 74134<br>Contact: Kyla Rudd 918/615-7233 | <b>FACILITY</b><br>- name and address where tanks are located:<br>QuikTrip #4431<br>8560 W 79th Street<br>Justice, IL 60458<br>Cook County<br>Contact: Kyla Rudd 918/615-7304 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**Tanks on the Permit**

| Tank # | Product            | Capacity | Tank Status        | Regulated Status |
|--------|--------------------|----------|--------------------|------------------|
| 1      | Gasoline - Regular | 15,000   | Tank Not Installed | Federal          |
| 2      | Gasoline - Regular | 15,000   | Tank Not Installed | Federal          |
| 3      | Gasoline - Regular | 15,000   | Tank Not Installed | Federal          |
| 4      | E15                | 15,000   | Tank Not Installed | Federal          |
| 5      | Gasoline - Premium | 15,000   | Tank Not Installed | Federal          |
| 6      | Diesel Fuel        | 15,000   | Tank Not Installed | Federal          |

## Tank 1 Equipment

| Equipment Type                | Permit Equipment                                                   | Action |
|-------------------------------|--------------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive                                             | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                           | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                         | New    |
| Leak Detection - Piping       | Siphon Bar                                                         | New    |
| Leak Detection - Tank         | Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                           | New    |
| Piping                        | Ball Valves                                                        | New    |
| Piping                        | Fiberglass Single Wall Piping Vent                                 | New    |
| Piping                        | Flex Connector Steel                                               | New    |
| Piping                        | Flexible Double Wall A.P.T. Poly Tech                              | New    |
| Piping                        | Shear Valves                                                       | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                       | New    |
| 🔧 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Piping                        | Single Wall Transition Sump                                        | New    |
| 🔧 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                           | New    |
| Tank                          | Fiberglass Brine Filled Double Wall XERXES                         | New    |

## Tank 2 Equipment

| Equipment Type                | Permit Equipment                                                   | Action |
|-------------------------------|--------------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive                                             | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                           | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                         | New    |
| Leak Detection - Piping       | Siphon Bar                                                         | New    |
| Leak Detection - Tank         | Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                           | New    |
| Piping                        | Ball Valves                                                        | New    |
| Piping                        | Fiberglass Single Wall Piping Vent                                 | New    |
| Piping                        | Flex Connector Steel                                               | New    |
| Piping                        | Flexible Double Wall A.P.T. Poly Tech                              | New    |
| Piping                        | Shear Valves                                                       | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                       | New    |
| 🔧 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Piping                        | Single Wall Transition Sump                                        | New    |
| 🔧 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                           | New    |
| Tank                          | Fiberglass Brine Filled Double Wall XERXES                         | New    |

### Tank 3 Equipment

| Equipment Type                | Permit Equipment                                                   | Action |
|-------------------------------|--------------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive                                             | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                           | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                         | New    |
| Leak Detection - Piping       | Siphon Bar                                                         | New    |
| Leak Detection - Tank         | Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                           | New    |
| Piping                        | Ball Valves                                                        | New    |
| Piping                        | Fiberglass Single Wall Piping Vent                                 | New    |
| Piping                        | Flex Connector Steel                                               | New    |
| Piping                        | Flexible Double Wall A.P.T. Poly Tech                              | New    |
| Piping                        | Shear Valves                                                       | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                       | New    |
| 🔌 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Piping                        | Single Wall Transition Sump                                        | New    |
| 🔌 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                           | New    |
| Tank                          | Fiberglass Brine Filled Double Wall XERXES                         | New    |

### Tank 4 Equipment

| Equipment Type                | Permit Equipment                                                   | Action |
|-------------------------------|--------------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive                                             | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                           | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                         | New    |
| Leak Detection - Tank         | Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                           | New    |
| Piping                        | Ball Valves                                                        | New    |
| Piping                        | Fiberglass Single Wall Piping Vent                                 | New    |
| Piping                        | Flex Connector Steel                                               | New    |
| Piping                        | Flexible Double Wall A.P.T. Poly Tech                              | New    |
| Piping                        | Shear Valves                                                       | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                       | New    |
| 🔌 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Piping                        | Single Wall Transition Sump                                        | New    |
| 🔌 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                           | New    |
| Tank                          | Fiberglass Brine Filled Double Wall XERXES                         | New    |

## Tank 5 Equipment

| Equipment Type                | Permit Equipment                                                   | Action |
|-------------------------------|--------------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive                                             | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                           | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                         | New    |
| Leak Detection - Tank         | Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                           | New    |
| Piping                        | Ball Valves                                                        | New    |
| Piping                        | Fiberglass Single Wall Piping Vent                                 | New    |
| Piping                        | Flex Connector Steel                                               | New    |
| Piping                        | Flexible Double Wall A.P.T. Poly Tech                              | New    |
| Piping                        | Shear Valves                                                       | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                       | New    |
| 🔍 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Piping                        | Single Wall Transition Sump                                        | New    |
| 🔍 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                           | New    |
| Tank                          | Fiberglass Brine Filled Double Wall XERXES                         | New    |

## Tank 6 Equipment

| Equipment Type                | Permit Equipment                                                   | Action |
|-------------------------------|--------------------------------------------------------------------|--------|
| Corrosion Protection - Piping | Flexible Non-Corrosive                                             | New    |
| Corrosion Protection - Tank   | Fiberglass Non-Corrosive                                           | New    |
| Leak Detection - Piping       | Electronic Pressurized Line Leak Detection                         | New    |
| Leak Detection - Tank         | Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor | New    |
| Overfill Prevention Device    | Overfill Drop Tube Valve                                           | New    |
| Piping                        | Ball Valves                                                        | New    |
| Piping                        | Fiberglass Single Wall Piping Vent                                 | New    |
| Piping                        | Flex Connector Steel                                               | New    |
| Piping                        | Flexible Double Wall A.P.T. Poly Tech                              | New    |
| Piping                        | Shear Valves                                                       | New    |
| Piping                        | Single Wall STP/Tanktop Sump                                       | New    |
| 🔍 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Piping                        | Single Wall Transition Sump                                        | New    |
| 🔍 Leak Detection - Piping     | Sump Sensor with positive shutdown                                 | New    |
| Spill Containment Device      | Double Wall Spill Bucket                                           | New    |
| Tank                          | Fiberglass Brine Filled Double Wall XERXES                         | New    |

## Dispensers on the Permit

| Dispenser | Action |
|-----------|--------|
| 1/2       | New    |
| 3/4       | New    |
| 5/6       | New    |
| 7/8       | New    |
| 9/10      | New    |
| 11/12     | New    |
| 13/14     | New    |
| 15/16     | New    |
| 17/18     | New    |

### Dispenser 1/2 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔌 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

### Dispenser 3/4 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔌 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

### Dispenser 5/6 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔌 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

### Dispenser 7/8 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔌 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

### Dispenser 9/10 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔌 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

### Dispenser 11/12 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔌 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

### Dispenser 13/14 Equipment

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| 🔌 Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 15/16 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Dispenser 17/18 Equipment**

| Equipment Type            | Permit Equipment                   | Action |
|---------------------------|------------------------------------|--------|
| Dispenser                 | Single Wall UDC Sump               | New    |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**General Requirements**

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**

Installing (6) 15k tanks, (1) canopy, APT piping, Bravo dispenser sumps, PCI tank sumps, TLS450+. The tanks will have a sump vent system installed through tank sumps with ball floats on each end.

**Special Contingencies**

**NOTES: Dispensers must be a full 10' from all buildings and property lines. Vents must meet section 175.440 of our rules.**

**PERSON, FIRM OR COMPANY PERFORMING WORK:**

Stenstrom Petroleum Services Group  
2422 Center Street  
Rockford, IL 61108

Contact Person: Robert Stenstrom  
Phone: 630/606-0996  
Email: nickb@rstenstrom.com  
Contractor License # IL1890 Exp. 4/12/2028

Sincerely,



Daniel Starks