



**Office of the Illinois State Fire Marshal**  
**Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov

**FOR OFFICE USE ONLY**  
Facility #: 7007983  
Permit #: 00740-2026UPG  
Request Rec'd: 06/18/2026  
Approval Date: 06/26/2026 DS  
Permit Expires: 12/29/2026

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

|                                                                                                                                                                                                                           |                                                                                                                                                                                                                            |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>OWNER OF TANKS</b><br>- Corporation, partnership, or other business entity:<br>SVC HYB Lease Pool 4 LLC<br>255 Washington Street Site 300<br>Newton, MA 02458<br>(None) County<br>Contact: Bonnie Parrino 216/219-2093 | <b>FACILITY</b><br>- name and address where tanks are located:<br>Travel Centers of America<br>4510 Broadway PO Box 943<br>Mount Vernon, IL 62864<br>Jefferson County<br>06-35-100-001<br>Contact: Lloyd Mays 440/808-7368 |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**Tanks on the Permit**

| Tank # | Product            | Capacity | Tank Status      | Regulated Status |
|--------|--------------------|----------|------------------|------------------|
| 5      | Gasoline - Regular | 20,000   | Currently in use | Federal          |
| 8      | Gasoline - Premium | 20,000   | Currently in use | Federal          |

**Tank 5 Equipment**

| Equipment Type          | Permit Equipment                   | Action |
|-------------------------|------------------------------------|--------|
| Piping                  | Single Wall STP/Tanktop Sump       | New    |
| Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

**Tank 8 Equipment**

| Equipment Type          | Permit Equipment                   | Action |
|-------------------------|------------------------------------|--------|
| Piping                  | Single Wall STP/Tanktop Sump       | New    |
| Leak Detection - Piping | Sump Sensor with positive shutdown | New    |

## Summary of Work

### DEMO

DEMO SURFACES AT REGULAR UNLEADED, PREMIUM UNLEADED AND T-3 DIESEL SUBMERSIBLE TURBINE PUMP'S (STP)

### REGULAR AND PREMIUM UNLEADED STP SUMPS

DISCONNECT EXISTING STP PIPING AND WIRE

INSTALL NEW TANK BUNG MOUNTED SUMPS

RE-INSTALL EXISTING STP'S

INSTALL NEW PRODUCT AND ELECTRICAL PENETRATIONS

INSTALL SENSOR CONDUIT AND WIRE FROM NEW REGULAR UNLEADED STP SUMP TO NEW PREMIUM UNLEADED STP SUMP

INSTALL PRODUCT PIPING TO POINT OF CONNECTION AT STP'S

INSTALL CONDUIT AND WIRE TO POINT OF CONNECTION AT STP'S

PURGE AIR FROM REGULAR UNLEADED AND PREMIUM UNLEADED PRODUCT PIPING

### T-3 DIESEL STP SUMP

INSTALL NEW CONDUIT PENETRATION

INSTALL SENSOR CONDUIT AND WIRE FROM T-3 DIESEL STP SUMP TO NEW REGULAR UNLEADED STP SUMP

### RESURFACING

BACKFILL AND RESURFACE TO MATCH EXISTING CONCRETE

### TESTING

PERFORM HYDROSTATIC TESTING AT T-3 DIESEL, REGULAR UNLEADED AND PREMIUM UNLEADED STP SUMPS


PERFORM PRE-BACKFILL PRESSURE TESTING OF REGULAR UNLEADED AND PREMIUM UNLEADED PRODUCT PIPING

PERFORM REQUIRED PRODUCT PIPING, LEAK DETECTOR AND SENSOR FUNCTIONALITY TESTING

## Special Contingencies

| PERSON, FIRM OR COMPANY PERFORMING WORK:                                          |                                                                                                                                               |
|-----------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|
| Jones Covey Group Inc<br>9595 Lucas Ranch Road #100<br>Rancho Cucamonga, CA 91730 | Contact Person: Jessica Holland<br>Phone: 909/730-9185<br>Email: steve.sills@jfpetrogroup.com<br>Contractor License # IL002414 Exp. 2/10/2027 |

Sincerely,



Daniel Starks

### For Office Use Only

#### Tank 5 Equipment

| Equipment Type | Permit Equipment               | Action   |
|----------------|--------------------------------|----------|
| Piping         | Not Installed STP/Tanktop Sump | Removing |

#### Tank 8 Equipment

| Equipment Type | Permit Equipment               | Action   |
|----------------|--------------------------------|----------|
| Piping         | Not Installed STP/Tanktop Sump | Removing |