



**Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 2048034
Permit #: 00745-2026INS
Request Rec'd: 06/15/2026
Approval Date: 06/29/2026 DS
Permit Expires: 12/29/2026

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted. The tank owner must submit a Notification for Underground Storage Tanks form prior to the scheduling of the final schedule at: <https://webapps.sfm.illinois.gov/USTPortal/NotificationForm>.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: QuikTrip Corporation 4705 S. 129th East Avenue Tulsa, OK 74134 Contact: Cody Thiems 918/615-7304	FACILITY - name and address where tanks are located: QuikTrip #4419 451 Riverstone Pkwy Kankakee, IL 60901 Kankakee County Contact: Kyla Rudd 918/655-7700
---	---

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	15,000	Tank Not Installed	Federal
2	Gasoline - Regular	15,000	Tank Not Installed	Federal
3	Gasoline - Regular	15,000	Tank Not Installed	Federal
4	E15	15,000	Tank Not Installed	Federal
5	Gasoline - Premium	15,000	Tank Not Installed	Federal
6	B-99	17,000	Tank Not Installed	Federal
7	Diesel Fuel	30,000	Tank Not Installed	Federal
8	Diesel Fuel	30,000	Tank Not Installed	Federal
9	Diesel Fuel	30,000	Tank Not Installed	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Piping	Siphon Bar	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Piping	Siphon Bar	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Piping	Siphon Bar	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔍 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔍 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 4 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔍 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔍 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 5 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 6 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Blending Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 7 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Piping	Siphon Bar	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Blending Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 8 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Piping	Siphon Bar	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Blending Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Tank 9 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Piping	Siphon Bar	New
Leak Detection - Tank	Hydrostatic Reservoir Interstitial Monitoring Sensors with monitor	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Blending Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Fiberglass Single Wall Piping Vent	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Single Wall Transition Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Brine Filled Double Wall XERXES	New

Dispensers on the Permit

Dispenser	Action
1/2	New
1D/2D	New
2D/3D	New
3/4	New
3D/4D	New
4D/5D	New
5/6	New
5D/6D	New
6D/7D	New
7/8	New
9/10	New
11/12	New
13/14	New
15/16	New

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
🔧 Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 1D/2D Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 2D/3D Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3D/4D Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 4D/5D Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5D/6D Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 6D/7D Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 13/14 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 15/16 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements

USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions. There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work

Installing (5) 15K gasoline, (3) 30K diesel, (1) 17K bio diesel, and (1) 10K DEF tank. (2) canopies, OPW Flexworks piping, PCI tank sumps, Bravo disepsner sumps, TLS450+. The auto and diesel tanks will have a sump vent system piped through them with a ball float on each end.

Special Contingencies

NOTES: Vents must meet section 175.440 of our rules. Dispensers must be at least 10' from all buildings and property lines.

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Stenstrom Petroleum Services Group 2422 Center Street Rockford, IL 61108	Contact Person: Robert Stenstrom Phone: 630/606-0996 Email: nickb@rstenstrom.com Contractor License # IL1890 Exp. 4/12/2028

Sincerely,



Daniel Starks