



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 7047294
Permit #: 00783-2026UPG
Request Rec'd: 07/08/2026
Approval Date: 07/08/2026 DS
Permit Expires: 01/08/2027

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity: Love's Travel Stops & Country Stores, Inc. 10601 N. Penn P.O. Box 26210 Oklahoma City, OK 73120 Contact: Kyle Collins 405/834-0311	FACILITY - name and address where tanks are located: Love's Travel Stop #824 3101 S. 10th Street Mount Vernon, IL 62864 Jefferson County 11-08-351-002 Contact: Morgan Archer 405/834-0311
---	--

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	20,000	Currently in use	Federal
2	Gasoline - Regular	12,000	Currently in use	Federal
3	Gasoline - Premium	8,000	Currently in use	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Piping	Siphon Bar	Removing
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve
Piping	Blending Sump	New
Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Flex Connector Steel	New
Piping	Flexible Double Wall Franklin Fueling Systems UPP - East	New
Piping	Other Steel Riser	New
Piping	Other Submersible Pump	New

Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Overfill Prevention Device	Overfill Drop Tube Valve	Replacing - Overfill Prev Device - Overfill Drop Tube Valve

Summary of Work

We will break out concrete over Siphon UNL, UNL, and Premium tanks and an electrical trench to building. We will install a dual meter blending sump, dual meter assembly, and a sump sensor. We will reroute UL siphon line into new dual meter sump. We will then run a new line from dual meter blending sump to Premium STP sump and connect onto the existing UNL piping. We will remove siphon suction leg and re-install it in the Premium STP Sump. We will nstall a new sub pump in Siphon UL sump for E98. New drop tubes will be installed in the E98 tank, UNL tank, and Prem tank. New conduits will be ran to the building.

Special Contingencies

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Illinois Oil Marketing Equipment, Inc. 850 Brenkman Drive Pekin, IL 61554	Contact Person: Bryan Estes Phone: 309/678-8061 Email: pcarrabbia@iome.com Contractor License # IL1293 Exp. 2/4/2028

Sincerely,



Daniel Starks