



**Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety**  
1035 Stevenson Drive  
Springfield, IL 62703  
217/785-1020  
www.sfm.illinois.gov  
SFM.DPCS@illinois.gov  
**Extended/Amended**

**FOR OFFICE USE ONLY**  
Facility #: 7039732  
Permit #: 01422-2025UPG  
Request Rec'd: 10/24/2025  
Approval Date: 10/27/2025 DS  
Amended Date: 08/03/2026 SB  
Extension Date: 04/22/2026  
Permit Expires: 10/28/2026

**Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for  
Petroleum and Hazardous Substances**

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to shall establish a date and time certain to perform the UST activity by scheduling the permitted activity through their UST contractor portal account. All testing forms must be submitted prior to the final being conducted.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE EXTENSION DATE.**

|                                                                                                                                                                                                          |                                                                                                                                                                                                          |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>OWNER OF TANKS</b><br>- Corporation, partnership, or other business entity:<br>Martin & Bayley, Inc.<br>P.O. Box 385<br>Carmi, IL 62821<br>White County<br>Contact: Landon Bayley 618/382-2334Ext.248 | <b>FACILITY</b><br>- name and address where tanks are located:<br>Hucks #349<br>201 East Main Street<br>Mount Vernon, IL 62864<br>Jefferson County<br>07-29-453-006<br>Contact: Norma McKay 618/382-2334 |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**Tanks on the Permit**

| Tank # | Product              | Capacity | Tank Status      | Regulated Status |
|--------|----------------------|----------|------------------|------------------|
| 1      | Gasoline - Regular   | 15,000   | Currently in use | Federal          |
| 2      | Gasoline - Regular   | 10,000   | Currently in use | Federal          |
| 3      | Gasoline - Mid-grade | 10,000   | Currently in use | Federal          |
| 4      | B-11                 | 4,000    | Currently in use | Federal          |
| 5      | Kerosene             | 4,000    | Currently in use | Federal          |

**Tank 1 Equipment**

| Equipment Type          | Permit Equipment                                          | Action                                                                                 |
|-------------------------|-----------------------------------------------------------|----------------------------------------------------------------------------------------|
| Leak Detection - Piping | Mechanical Pressurized Line Leak Detection                | Replacing - Leak Detect - Piping - Mechanical Pressurized Line Leak Detection          |
| Leak Detection - Tank   | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 300j with CSLD |
| Piping                  | Flexible Double Wall OPW Flexworks                        | Replacing - Piping - Flexible Double Wall Total Containment Omniflex II                |
| Piping                  | Polyethylene Chase                                        | New                                                                                    |
| Piping                  | Single Wall STP/Tanktop Sump                              | Replacing - Piping - Single Wall STP/Tanktop Sump                                      |
| Leak Detection - Piping | Sump Sensor with positive shutdown                        | New                                                                                    |

**Tank 2 Equipment**

| <b>Equipment Type</b>                                                                                     | <b>Permit Equipment</b>                                   | <b>Action</b>                                                                          |
|-----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|----------------------------------------------------------------------------------------|
| Leak Detection - Piping                                                                                   | Mechanical Pressurized Line Leak Detection                | Replacing - Leak Detect - Piping - Mechanical Pressurized Line Leak Detection          |
| Leak Detection - Tank                                                                                     | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 300j with CSLD |
| Piping                                                                                                    | Flexible Double Wall OPW Flexworks                        | Replacing - Piping - Flexible Double Wall Total Containment Omniflex II                |
| Piping                                                                                                    | Polyethylene Chase                                        | New                                                                                    |
| Piping                                                                                                    | Single Wall STP/Tanktop Sump                              | Replacing - Piping - Single Wall STP/Tanktop Sump                                      |
|  Leak Detection - Piping | Sump Sensor with positive shutdown                        | New                                                                                    |

**Tank 3 Equipment**

| <b>Equipment Type</b>                                                                                     | <b>Permit Equipment</b>                                   | <b>Action</b>                                                                          |
|-----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|----------------------------------------------------------------------------------------|
| Leak Detection - Piping                                                                                   | Mechanical Pressurized Line Leak Detection                | Replacing - Leak Detect - Piping - Mechanical Pressurized Line Leak Detection          |
| Leak Detection - Tank                                                                                     | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 300j with CSLD |
| Piping                                                                                                    | Flexible Double Wall OPW Flexworks                        | Replacing - Piping - Flexible Double Wall Total Containment Omniflex II                |
| Piping                                                                                                    | Polyethylene Chase                                        | New                                                                                    |
| Piping                                                                                                    | Single Wall STP/Tanktop Sump                              | Replacing - Piping - Single Wall STP/Tanktop Sump                                      |
|  Leak Detection - Piping | Sump Sensor with positive shutdown                        | New                                                                                    |

**Tank 4 Equipment**

| <b>Equipment Type</b>                                                                                       | <b>Permit Equipment</b>                                   | <b>Action</b>                                                                          |
|-------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|----------------------------------------------------------------------------------------|
| Leak Detection - Piping                                                                                     | Mechanical Pressurized Line Leak Detection                | Replacing - Leak Detect - Piping - Mechanical Pressurized Line Leak Detection          |
| Leak Detection - Tank                                                                                       | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 300j with CSLD |
| Piping                                                                                                      | Flexible Double Wall OPW Flexworks                        | Replacing - Piping - Flexible Double Wall Total Containment Omniflex II                |
| Piping                                                                                                      | Polyethylene Chase                                        | New                                                                                    |
| Piping                                                                                                      | Single Wall STP/Tanktop Sump                              | Replacing - Piping - Single Wall STP/Tanktop Sump                                      |
|  Leak Detection - Piping | Sump Sensor with positive shutdown                        | New                                                                                    |
| Spill Containment Device                                                                                    | Double Wall Spill Bucket                                  | Replacing - Spill Contain Device - Single Wall Spill Bucket                            |

## Tank 5 Equipment

| Equipment Type                                                                                            | Permit Equipment                                          | Action                                                                                 |
|-----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|----------------------------------------------------------------------------------------|
| Leak Detection - Piping                                                                                   | Mechanical Pressurized Line Leak Detection                | Replacing - Leak Detect - Piping - Mechanical Pressurized Line Leak Detection          |
| Leak Detection - Tank                                                                                     | Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD | Replacing - Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 300j with CSLD |
| Piping                                                                                                    | Flexible Double Wall OPW Flexworks                        | Replacing - Piping - Flexible Double Wall Total Containment Omniflex II                |
| Piping                                                                                                    | Polyethylene Chase                                        | New                                                                                    |
| Piping                                                                                                    | Single Wall STP/Tanktop Sump                              | Replacing - Piping - Single Wall STP/Tanktop Sump                                      |
|  Leak Detection - Piping | Sump Sensor with positive shutdown                        | New                                                                                    |
| Spill Containment Device                                                                                  | Double Wall Spill Bucket                                  | Replacing - Spill Contain Device - Single Wall Spill Bucket                            |

## Dispensers on the Permit

| Dispenser | Action                      |
|-----------|-----------------------------|
| 1/2       | Sump and/or Sensor Changing |
| 3/4       | Sump and/or Sensor Changing |
| 5/6       | Sump and/or Sensor Changing |
| 7/8       | Sump and/or Sensor Changing |
| 9/10      | Sump and/or Sensor Changing |
| 11/12     | Sump and/or Sensor Changing |
| 13/14     | Sump and/or Sensor Changing |

## Dispenser 1/2 Equipment

| Equipment Type                                                                                              | Permit Equipment                   | Action                                       |
|-------------------------------------------------------------------------------------------------------------|------------------------------------|----------------------------------------------|
| Dispenser                                                                                                   | Single Wall UDC Sump               | Replacing - Dispenser - Single Wall UDC Sump |
|  Leak Detection - Piping | Sump Sensor with positive shutdown | New                                          |

## Dispenser 3/4 Equipment

| Equipment Type                                                                                              | Permit Equipment                   | Action                                       |
|-------------------------------------------------------------------------------------------------------------|------------------------------------|----------------------------------------------|
| Dispenser                                                                                                   | Single Wall UDC Sump               | Replacing - Dispenser - Single Wall UDC Sump |
|  Leak Detection - Piping | Sump Sensor with positive shutdown | New                                          |

## Dispenser 5/6 Equipment

| Equipment Type                                                                                              | Permit Equipment                   | Action                                       |
|-------------------------------------------------------------------------------------------------------------|------------------------------------|----------------------------------------------|
| Dispenser                                                                                                   | Single Wall UDC Sump               | Replacing - Dispenser - Single Wall UDC Sump |
|  Leak Detection - Piping | Sump Sensor with positive shutdown | New                                          |

## Dispenser 7/8 Equipment

| Equipment Type                                                                                              | Permit Equipment                   | Action                                       |
|-------------------------------------------------------------------------------------------------------------|------------------------------------|----------------------------------------------|
| Dispenser                                                                                                   | Single Wall UDC Sump               | Replacing - Dispenser - Single Wall UDC Sump |
|  Leak Detection - Piping | Sump Sensor with positive shutdown | New                                          |

## Dispenser 9/10 Equipment

| Equipment Type                                                                                              | Permit Equipment                   | Action                                       |
|-------------------------------------------------------------------------------------------------------------|------------------------------------|----------------------------------------------|
| Dispenser                                                                                                   | Single Wall UDC Sump               | Replacing - Dispenser - Single Wall UDC Sump |
|  Leak Detection - Piping | Sump Sensor with positive shutdown | New                                          |

**Dispenser 11/12 Equipment**

| Equipment Type          | Permit Equipment                   | Action                                       |
|-------------------------|------------------------------------|----------------------------------------------|
| Dispenser               | Single Wall UDC Sump               | Replacing - Dispenser - Single Wall UDC Sump |
| Leak Detection - Piping | Sump Sensor with positive shutdown | New                                          |

**Dispenser 13/14 Equipment**

| Equipment Type          | Permit Equipment                   | Action                                       |
|-------------------------|------------------------------------|----------------------------------------------|
| Dispenser               | Single Wall UDC Sump               | Replacing - Dispenser - Single Wall UDC Sump |
| Leak Detection - Piping | Sump Sensor with positive shutdown | New                                          |

**Summary of Work**

Remove all existing stp and dispenser sumps and replace with new. Run all new piping and conduits and add sump sensors with positive shutdown.

Amending permit to add the replacement of the diesel and K-1 spill buckets.

**Special Contingencies****Amendment Reason #1:**


Replacing spill buckets on diesel and K-1 tank due to being so close to newly installed STP sumps.

**Amendment Reason #2:**

Adding replacement of existing veeder Root t1s-350 with a veeder Root t1s-450 plus

| PERSON, FIRM OR COMPANY PERFORMING WORK:                                                        |                                                                                                                               |
|-------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------|
| Hinderliter Construction & Maint., Inc.<br>3601 North St. Joseph Avenue<br>Evansville, IN 47720 | Contact Person: Mark Hinderliter<br>Phone: 812/425-4137<br>Email: mark.k@hci4.com<br>Contractor License # IL646 Exp. 7/3/2026 |

Sincerely,



Daniel Starks

**For Office Use Only****Tank 1 Equipment**

| Equipment Type          | Permit Equipment                                                               | Action   |
|-------------------------|--------------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

**Tank 2 Equipment**

| Equipment Type          | Permit Equipment                                                               | Action   |
|-------------------------|--------------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

**Tank 3 Equipment**

| Equipment Type          | Permit Equipment                                                               | Action   |
|-------------------------|--------------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

**Tank 4 Equipment**

| Equipment Type          | Permit Equipment                                                               | Action   |
|-------------------------|--------------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

**Tank 5 Equipment**

| Equipment Type          | Permit Equipment                                                               | Action   |
|-------------------------|--------------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall STP/Tanktop Sump | Removing |

**Dispenser 1/2 Equipment**

| Equipment Type          | Permit Equipment                                                       | Action   |
|-------------------------|------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

**Dispenser 3/4 Equipment**

| Equipment Type          | Permit Equipment                                                       | Action   |
|-------------------------|------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

**Dispenser 5/6 Equipment**

| Equipment Type          | Permit Equipment                                                       | Action   |
|-------------------------|------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

**Dispenser 7/8 Equipment**

| Equipment Type          | Permit Equipment                                                       | Action   |
|-------------------------|------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

**Dispenser 9/10 Equipment**

| Equipment Type          | Permit Equipment                                                       | Action   |
|-------------------------|------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

**Dispenser 11/12 Equipment**

| Equipment Type          | Permit Equipment                                                       | Action   |
|-------------------------|------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |

**Dispenser 13/14 Equipment**

| Equipment Type          | Permit Equipment                                                       | Action   |
|-------------------------|------------------------------------------------------------------------|----------|
| Leak Detection - Piping | Piping Sump Sensors Not Regulated Not Required in Single Wall UDC Sump | Removing |