Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov
Extended

FOR OFFICE USE ONLY

Facility #:	2014602
Permit #:	00291-2026INS
Request Rec'd:	03/16/2026
Approval Date:	03/16/2026 DS
Extension Date:	08/19/2026
Permit Expires:	03/16/2027

Permit for INSTALLATION of Regulated Underground Storage Tanks and Piping

Permission is hereby granted to install the underground storage tank(s) and associated piping identified below. All installation activities must be conducted in accordance with all applicable sections of 41 Ill. Adm. Code Parts 174, 175, and 176. The permitted contractor must schedule specific dates and times for all required activities through their contractor portal account. Both the electronic testing forms and the Notification for Underground Storage Tank form must be submitted before the final inspection can be scheduled.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE EXTENSION DATE.

OWNER OF TANKS
- Corporation, partnership, or other business entity:

Speedway, LLC
P.O. Box 1500
Springfield, OH 45501
Clark County

Contact: Zachery Davis 937/203-7827

FACILITY
- name and address where tanks are located:

Speedway #7757
3040 W 95Th
Evergreen Park, IL 60805
Cook County
24-01-324-048-0000

Contact: Kelly Reid 708/424-6889

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
22	Gasoline - Regular	20,000	Tank Not Installed	Federal
23	Diesel Fuel	12,000	Tank Not Installed	Federal
24	Gasoline - Premium	8,000	Tank Not Installed	Federal

Tank 22 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Piping	Polyethylene Chase	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Extractor Fitting Valves	New
Piping	Fiberglass Single Wall Piping A.O. Smith	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Other Submersible Pump	New
Piping	Polyethylene Chase	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Tank Steel Riser	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 23 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Piping	Polyethylene Chase	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Extractor Fitting Valves	New
Piping	Fiberglass Single Wall Piping A.O. Smith	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Other Submersible Pump	New
Piping	Polyethylene Chase	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Tank Steel Riser	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Tank 24 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Fiberglass Non-Corrosive	New
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Piping	Polyethylene Chase	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Drop Tube Valve	New
Piping	Ball Valves	New
Piping	Extractor Fitting Valves	New
Piping	Fiberglass Single Wall Piping A.O. Smith	New
Piping	Flexible Double Wall OPW Flexworks	New
Piping	Other Submersible Pump	New
Piping	Polyethylene Chase	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Tank Steel Riser	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall XERXES	New

Dispensers on the Permit

Dispenser	Action
1/2	Sump and/or Sensor Changing
3/4	Sump and/or Sensor Changing
5/6	Sump and/or Sensor Changing
7/8	Sump and/or Sensor Changing
9/10	Sump and/or Sensor Changing
11/12	Sump and/or Sensor Changing

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements
USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.
There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work
We are installing (2) Xerxes tanks. 1-20k regular tank, 1-12k Diesel/8k-Premium tank. Installing all assoicated OPW doublewall flexworks piping, and smith single wall vent piping. Installing (4) new OPW dispenser sumps.

Special Contingencies
NOTES: Dispensers must be a full 10' from all buildings and property lines. Vents must meet section 175.440 of our rules.

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Anderson Pump Service, Inc. 19659 South 97th Avenue Mokena, IL 60448	Contact Person: Ron Anderson Phone: 630/484-7374 Email: KeenanA@Andersonpump.com Contractor License # IL002275 Exp. 5/21/2026

Sincerely,

Daniel Starks

For Office Use Only

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing

Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Not Installed UDC Sump	Removing