Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov
Extended/Revised/Amended

FOR OFFICE USE ONLY
Facility #: 2048010
Permit #: 00476-2026INS
Request Rec'd: 04/27/2026
Approval Date: 04/28/2026 DS
Amended Date:10/20/2026 DS
Extension Date: 10/22/2026
Revision Date: 10/20/2026 DS
Permit Expires: 04/28/2027

Permit for INSTALLATION of Regulated Underground Storage Tanks and Piping

Permission is hereby granted to install the underground storage tank(s) and associated piping identified below. All installation activities must be conducted in accordance with all applicable sections of 41 Ill. Adm. Code Parts 174, 175, and 176. The permitted contractor must schedule specific dates and times for all required activities through their contractor portal account. Both the electronic testing forms and the Notification for Underground Storage Tank form must be submitted before the final inspection can be scheduled.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE EXTENSION DATE.

OWNER OF TANKS
- Corporation, partnership, or other business entity:

Lucky Supermarket Inc
945 Willowbrook Dr
Schererville, IN 46375

Contact: Paramvir Singh 641/275-2103

FACILITY
- name and address where tanks are located:

Lucky Supermarket Inc
19501 Torrence Ave
Lynwood, IL 60411
Cook County
33-07-100-035-0000

Contact: Paramvir Singh 641/275-2103

Tanks on the Permit

Tank #	Product	Capacity	Tank Status	Regulated Status
1	Gasoline - Regular	30,000	Installed/Not in Use	Federal
2	Gasoline - Premium	10,000	Installed/Not in Use	Federal
3	Diesel Fuel	10,000	Installed/Not in Use	Federal

Tank 1 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Ball Valves	New
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	New
Piping	Flexible Single Wall Piping	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Tank Steel Riser	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Fiberglass Tank Solutions	New

Tank 2 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Ball Valves	New
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	New
Piping	Flexible Single Wall Piping	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Tank Steel Riser	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Fiberglass Tank Solutions	New

Tank 3 Equipment

Equipment Type	Permit Equipment	Action
Corrosion Protection - Piping	Flexible Non-Corrosive	New
Corrosion Protection - Tank	Fiberglass Non-Corrosive	New
Leak Detection - Piping	Electronic Pressurized Line Leak Detection	New
Leak Detection - Tank	Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD	New
Leak Detection - Tank	Non-Discriminating Interstitial Monitoring Sensors	New
Overfill Prevention Device	Overfill Alarm	New
Piping	Ball Valves	New
Piping	Flexible Double Wall A.P.T. Poly Tech P150SC	New
Piping	Flexible Single Wall Piping	New
Piping	Other Submersible Pump	New
Piping	Shear Valves	New
Piping	Single Wall STP/Tanktop Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New
Piping	Tank Steel Riser	New
Spill Containment Device	Double Wall Spill Bucket	New
Tank	Fiberglass Double Wall Fiberglass Tank Solutions	New

Dispensers on the Permit

Dispenser	Action
1/2	New
3/4	New
5/6	New
7/8	New
9/10	New
11/12	New
13/14	New
15/16	New
17/18	New
19/20	New

Dispenser 1/2 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 3/4 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 5/6 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 7/8 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 9/10 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 11/12 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 13/14 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 15/16 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 17/18 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

Dispenser 19/20 Equipment

Equipment Type	Permit Equipment	Action
Dispenser	Single Wall UDC Sump	New
↳ Leak Detection - Piping	Sump Sensor with positive shutdown	New

General Requirements
USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.
There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

Summary of Work
Building new site, installing new tank monitor, tanks, piping, sumps, and single wall vent piping.

Special Contingencies

Amendment Reason:
Correct tank manufacturer

Revision Reason:
Changed tank manufacturer to tank solutions

PERSON, FIRM OR COMPANY PERFORMING WORK:	
B & K Equipment Company 2939 175th Street Lansing, IL 60438	Contact Person: DJ White Phone: 708/474-3344 Email: dj.white@bkequip.com Contractor License # IL1207 Exp. 2/14/2028

Sincerely,

Daniel Starks